

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-175-20333-00-00
Spot: E2NWNW Sec/Twnshp/Rge: 15-35S-32W
660 feet from N Section Line, 1245 feet from W Section Line
Lease/Unit Name: LIGHT Well Number: 2
County: SEWARD Total Vertical Depth: 6300 feet

Operator License No.: 32724
Op Name: TEKENERGY, INC.
Address: 6801 N BROADWAY, SUITE 226
OKLAHOMA CITY, OK 73116

Conductor Pipe: Size feet:
Surface Casing: Size 8.625 feet: 1469 WITH 800 SX CMT
Production: Size 4.5 feet: 6298 WITH 325 SX CMT
Liner: Size feet: \$204.75

Well Type: GAS UIC Docket No: Date/Time to Plug: 08/21/2001 9:00 AM
Plug Co. License No.: 31151 Plug Co. Name: SARGENT AND HORTON PLUGGING, INC.
Proposal Rcvd. from: DON HORTON Company: SARGENT AND HORTON PLUGGIN Phone: (580) 854-6515

Proposed Plugging Method: 1ST PLUG AT 2570' WITH 50 SX CMT. 2ND PLUG AT 1500' WITH 50 SX CMT. 3RD PLUG AT 720' WITH 25 SX CMT. 4TH PLUG AT 40-0' WITH 10 SX CMT.

Plugging Proposal Received By: STEVE DURRANT Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 08/21/2001 4:00 PM KCC Agent: JIM HOLLAND

Actual Plugging Report:

PERFS AT 6102-6128, 5065-5067'. CIBP @ 6056' WITH 2 SX CMT. LOAD HOLE WITH 40 BBL MUD. 1ST PLUG AT 2570' WITH 50 SX CMT. 2ND PLUG PULL OUT OF HOLE WITH 4 1/2' CASING TO 1500' PUMP 50 SX CMT. 3RD PLUG PULL OUT OF HOLE WITH 4 1/2" CASING TO 720' PUMP 25 SX CMT. 4TH PLUG PULL OUT OF HOLE WITH 4 1/2" CASING TO 40' WITH 10 SX CMT.

RECEIVED
SEP 07 2001
KCC WICHITA

Remarks: USED COMMON CEMENT BY SARGENTS. RECOVERED 2600' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed Jim Holland PART II
(TECHNICIAN)

INVOICED SEP 06 2001

DATE 9-7-01

INV. NO. 2002060425 MP

Form CR 23