

1 020288

1-22

307 R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION N/2 SE NE NE, SEC. 12, T 35 S, R 32 W/E  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 175-20,824-0000

4440 feet from S section line  
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 3988

Lease Name Lofland Well # 1-12

Operator: Slawson Exploration Company  
Name & Address 20 North Broadway, Suite 700  
Oklahoma City, OK 73102

County Seward 216.13

Well Total Depth 6650 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1525

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Sargent's Casing Pulling Service License Number 6547

Address P.O. Box 506, Liberal, KS 67905-0506

Company to plug at: Hour: 9:30 a.m. Day: 18 Month: 1 Year: 19 90

Plugging proposal received from Doug Blair

(company name) Sargent's Casing Pulling Service (phone) 316-624-7455

were: 4 1/2" at 6647' PBDT 6563' Perfs at 5959-63, 6257-6301, 6111-36' CIBP at 6050'

1st plug pump 1 sx hulls and 20 sx cement to 5900',

2nd plug pump 50 sx cement at 1550',

3rd plug pump 40 sx cement at 700',

4th plug pump 10 sx cement at 40'.

Plugging Proposal Received by Richard Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 11 a.m. Day: 22 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement at perfs, TOC 5760', Hole loaded with heavy mud:

2nd plug pumped 50 sx cement at 1550'

3rd plug pumped 40 sx cement at 650',

4th plug pumped 10 sx cement at 40-0'.

RECEIVED STATE CORPORATION COMMISSION

JAN 30 1990

CONSERVATION DIVISION Wichita, Kansas

Remarks: Used common cement by Sargent's. Recovered 2814' of 4 1/2" casing. (if additional description is necessary, use BACK of this form.)

INVOICED

DATE FEB 07 1990

INV. NO. 27359

Signed Glenn R. Barlow (TECHNICIAN)