

1 050741

API NUMBER 15- 175-20,892-0000

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

C NW SE, SEC. 9, T 35 S, R 32 ^{W/2}

1980 feet from S section line

1980 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5181

Lease Name Thompson Well # 1-9

Operator: Donald C. Slawson

County Seward 204.75

Name & Address 20 N. Broadway, Suite 700

Well Total Depth 6300 Chester feet

Oklahoma City, OK 73102

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 1503

Abandoned Oil Well Gas Well Input Well SWD Well D&A x

Other well as hereinafter indicated

Plugging Contractor Slawson Drilling Co., Inc. License Number 5657

Address P. O. Box 1409, Great Bend, KS 67530

Company to plug at: Hour: 11:00 pm Day: 5 Month: January Year: 19 86

Plugging proposal received from Jim Loftis

(company name) Slawson (phone) 316-793-3561

were: to fill hole with heavy mud and spot cement through drill pipe Anhydrite N/A 8 5/8" set through Anhydrite

1st plug at 2700' with 100 sx cement

2nd plug at 1540' with .50 sx cement

3rd plug at 750' with 40 sx cement solid bridge

4th plug hulls - plug at 40' -- cement to surface with 10 sx cement

6th plug to circulate rathole with 15 sx cement Plugging Proposal Received by Richard W. Lacey (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 1:00 am Day: 6 Month: January Year: 19 86

ACTUAL PLUGGING REPORT 1st plug at 2700' with 100 sx cement, 2nd plug at 1540' with 50 sx cement, 3rd plug at 750' with 40 sx cement, 4th & 5th plugs - solid bridge - hulls - plug at 40' -- cement to surface with 10 sx cement, 6th plug to circulate rat hole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton # 090750 (If additional description is necessary, use BACK of this form.)

INVOICED

DATE JAN 14 1986

INV. NO. 1209

MAR 07 1986

RECEIVED STATE CORPORATION COMMISSION

Signed Richard W. Lacey (TECHNICIAN)

JAN 13 1986

CONSERVATION DIVISION Wichita Kansas

FORM CP-2/3 Rev. 01-84

1-6