

1300260

TO: STATE CORPORATION COMMISSION

11-2

API NUMBER 15-175-10,203-0000
C SW SW SEC. 9, T 35 S, R 32 W

CONSERVATION DIVISION - PLUGGING SECTION 660 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 660 FEET FROM WEST SECTION LINE

WICHITA, KANSAS 67202 LEASE NAME LIGHT UNIT WELL # B-1

TECHNICIAN'S PLUGGING REPORT COUNTY SEWARD 203.78

OPERATOR LICENSE # 7123 WELL TOTAL DEPTH 6270 FEET

OPERATOR: H.I., INC PRODUCTION CSG: SIZE 5 1/2" @ 6270' WITH 150 SX

NAME AND 110 W 3RD SURFACE CASING: SIZE 8 5/8" @ 2478' WITH 150 SX

ADDRESS LIBERAL, KS 67905 CONDUCTOR CSG: SIZE 13 3/8" @ 489' WITH 450 SX

ABANDONED OIL WELL X GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR SARGENTS CSG. PULLING LICENSE NUMBER 6547

ADDRESS PO BOX 506 LIBERAL, KS 67901-0506

COMPANY TO PLUG AT: HOUR: 9:00 AM DAY: 02 MONTH: 11 YEAR: 1998

PLUGGING PROPOSAL RECEIVED FROM KIRBY/ BOB SARGENTS

(COMPANY NAME) SARGENTS CASING PULLING (PHONE) 316-624-7455

WERE: PERFS AT 4560-4574.DV TOOL @ 4689' W/150 SX. TOC @ 4100'.

SET CIBP @ 4660'. 1ST PLUG SPOT 25 SX CEMENT WITH 200# HULLS FROM 4500'-4320'.

2ND PLUG SPOT 50 SX PLUG @ 637'. PULL 8 5/8" OUT. LET STAND. TAG CEMENT @ 595'.

3RD PLUG SPOT 70 SX PLUG AT 490'. 4TH PLUG SPOT 25 SX CEMENT AT 40' TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL X PART NONE

OPERATIONS COMPLETED: HOUR: 5:00 PM DAY: 02 MONTH: 11 YEAR: 1998

ACTUAL PLUGGING REPORT

ON 10-28-98 SET CIBP @ 4660'. 1ST PLUG SPOT 25 SX CEMENT WITH 200# HULLS FROM 4500' TO

4320'. 2ND PLUG SPOT 50 SX PLUG AT 637'. PULL 8 5/8" OUT. LET STAND. TAG CEMENT AT 595'.

3RD PLUG SPOT 70 SX PLUG AT 490'. 4TH PLUG SPOT 25 SX AT 40' TO SURFACE.

11-5-98

REMARKS: USED COMMON CEMENT BY SARGENTS RECOVERED 2825' OF 5 1/2" CASING & 637' OF 8 5/8" CSG.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

SIGNED Gary Winters (TECHNICIAN) FORM CP-2/3

60267