

To: 1 020719 11-10
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20, 335 - 0000
SE SE NW, SEC. 6, T 35 S, R 32
2970 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 7123
Operator: H.I. Inc.
Name & Address: P.O. Box 2526
Liberal, KS 67905-2526

Lease Name Brown V A.E. Well # 1
County Seward
Well Total Depth 6470 219.05 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 1549

Abandoned Oil Well _____ Gas Well Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Sargent & Horton Plugging Inc. License Number 31151
Address Rt. 1, Box 49BA, Tyrone, OK 73951-9731

Company to plug at: Hour: 4 p.m. Day: 9 Month: 11 Year: 1993

Plugging proposal received from Don Horton
(company name) Sargent & Horton Plugging Inc. (phone) 405-854-6515

were: 4 1/2" at 6463' w/400 sx cement, Perfs at 6414-22, 6029-39'
1st plug pump 2 sx hulls and 20 sx cement at perfs,
2nd plug pump 25 sx cement at 1800',
3rd plug pump 50 sx cement at 1580',
4th plug pump 40 sx cement at 700', 5th plug pump 10 sx cement at 40 to -4'.

Plugging Proposal Received by Glenn Barlow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____
Operations Completed: Hour: 4:30 p.m. Day: 10 Month: 11 Year: 1993

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 20 sx cement at perfs,
2nd plug pumped 25 sx cement at 1800', stub plug,
3rd plug pump 50 sx cement at 1580',
4th plug pump 40 sx cement at 700',
5th plug pump 10 sx cement at 40 to -4'.

RECEIVED
STATE CORPORATION COMMISSION
NOV 17 1993

Mud between all plugs.
Remarks: Used common cement by Sargent & Horton. Recovered 2810' of 4 1/2" casing.

INVOICED (If additional description is necessary, use BACK of this form.)
I (did / did not) observe this plugging.
DATE: 11-19-93
INV. NO. 39055
Signed Glenn R. Barlow (TECHNICIAN)