

1
060446

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION App. C E/2, SEC. 3, T 35 S, R 32 W/R
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-175-20,817-0000

2620 feet from S section line

1550 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5703

Lease Name Light "J" Well # 1

Operator: J. M. Huber Corporation

County Seward 204.75

Name & Address 7120 I-40 @ 3w5

Well Total Depth 6300 feet

Amarillo, TX 79106

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 150

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ O&A

Other well as hereinafter indicated _____

Plugging Contractor Johnson Drilling Company, Inc. License Number 7860

Address 3535 NW 58th Street, Suite 710, Oklahoma City, OK 73112

Company to plug at: Hour: 4:00 am Day: 26 Month: December Year: 19 84

Plugging proposal received from Jerry Trout

(company name) Johnson Drilling (phone) 405-943-7667

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1550' with 50 sx cement

2nd plug at 760' with 50 sx cement

3rd plug solid bridge
hulls - plug at 40' -- cement to surface with 10 sx cement

5th plug to circulate rat hole with 15 sx cement

6th plug to circulate mouse hole with 10 sx cement

Plugging Proposal Received by Paul A. Luthis
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:00 am Day: 26 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 1st plug at 1550' with 50 sx cement, 2nd plug at 760' with 50

sx cement, 3rd & 4th plugs - solid bridge - hulls - plug at 40' -- cement to surface

with 10 sx cement, 5th plug to circulate rat hole with 15 sx cement, 6th-plug to

circulate mouse hole with 10 sx cement.

STATE CORPORATION COMMISSION

JAN 02 1985

CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used 60/40 Pozmix 2% gel 3% cc by B.J.

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 1-15-85

Signed Paul A. Luthis
(TECHNICIAN)

INV. NO. 6457