

1100336

TO: STATE CORPORATION COMMISSION

API NUMBER 15-175-00400-0000  
SW NW NW SEC. 6, T 35 S, R 33 W

CONSERVATION DIVISION - PLUGGING SECTION 4030 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 4760 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME LIBERAL WELL # 4

TECHNICIAN'S PLUGGING REPORT 3/9

COUNTY SEWARD 88.56

OPERATOR LICENSE # 4782

WELL TOTAL DEPTH 2725 FEET

OPERATOR: ENSIGN OPERATING CO. PRODUCTION CSG: SIZE 7" @ 2724' WITH 700 SX

NAME AND PO BOX 2161 SURFACE CASING: SIZE 9 5/8" @ 699' WITH 425 SX

ADDRESS LIBERAL, KS 67905-2161

ABANDONED OIL WELL  GAS WELL  INPUT WELL  SWD WELL  D/A

OTHER WELL AS HEREINAFTER INDICATED \_\_\_\_\_

PLUGGING CONTRACTOR BRUCE WELL SERVICE LICENSE NUMBER 7407

ADDRESS PO BOX 1597 LIBERAL, KS 67905-1597

COMPANY TO PLUG AT: HOUR: 10:00 AM DAY: 06 MONTH: 03 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM \_\_\_\_\_

(COMPANY NAME) BRUCE WELL SERVICE (PHONE) 316-624-1904

WERE: PERFS AT 2652-2690

TUBING STUCK. RODS PARTED AT 600'. RUN 1 1/4 ROD WITH OVERSHOT. PULL ROD TO 2250', RODS PARTED. SHOOT TUBING AT 1002'. SET CIBP AT 950' WITH 4 SX CEMENT ON TOP. PERFORATE AT 700'. SET CEMENT PLUG AT 700' TO SURFACE LEAVING ANNULUS 9 5/8 X 7" FULL TO SURFACE AND 7" CASING FULL TO SURFACE.

PLUGGING PROPOSAL RECEIVED BY GARY WINTERS

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL  PART \_\_\_\_\_ NONE \_\_\_\_\_

OPERATIONS COMPLETED: HOUR: 11:30 PM DAY: 09 MONTH: 03 YEAR: 2000

ACTUAL PLUGGING REPORT \_\_\_\_\_

TUBING STUCK. RODS PARTED AT 600'. RUN 1 1/4 ROD WITH OVERSHOT. PULL ROD TO 2250', RODS PARTED. SHOOT TUBING AT 1002'. SET CIBP AT 950' WITH 4 SX CEMENT ON TOP. PERFORATE AT 700'. SET CEMENT PLUG AT 700' TO SURFACE LEAVING ANNULUS 9 5/8 X 7" FULL TO SURFACE AND 7" CASING FULL TO SURFACE.

RECEIVED  
STATE CORPORATION COMMISSION


REMARKS: USED 260 SX OF 65/35 POZMIX CEMENT BY HALLIBURTON. NO CASING RECOVERED.  
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING.

INVOICED

DATE 3/29/00 SIGNED \_\_\_\_\_

INV. NO. 061477

CONSERVATION DIVISION  
Wichita, Kansas  
SIGNED Gary Winters  
(TECHNICIAN) FORM CP-2/3 

MAR 27 2000