

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-21048-0000

LEASE NAME ADAMS

WELL NUMBER 2-12

2989 Ft. from S Section Line

829 Ft. from E Section Line

SEC. 12 TWP. 35S RGE. 29 (X) or (W)

COUNTY MEADE

Date Well Completed 5/10/01

Plugging Commenced 5/10/01

Plugging Completed 5/10/01

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR PARDEE PRODUCTION Co.

ADDRESS 7706 E. 85TH ST., TULSA, OK

PHONE# (918) 459-0522 OPERATORS LICENSE NO. 31361

Character of Well D&A

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 5/10/01 (date)

by STEVE MIDDLETON (KCC District Agent's Name).

Is ACO-1 filed? YES If not, is well log attached? _____

Producing Formation N/A Depth to Top _____ Bottom _____

Show depth and thickness of all water, oil and gas formations.

RECEIVED
KANSAS CORPORATION COMMISSION

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From SURF	To	Size	Put in	Pulled out
CHASE	WET	SURF	56'	20"	56'	0'
COUNCIL GROVE	WET	SURF	1475'	8-5/8"	1475'	CONSERVATION DIVISION

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set.

NEWLY DRILLED HOLE FULL OF MUD (CHLORIDES < 4000 ppm).
PLUG #1: FROM 1500' - 1350', SPOT 50SX @ 1500' w/ DRILL PIPE
PLUG #2: FROM 500' - 390', SPOT 40SX @ 500' w/ DRILL PIPE
PLUG #3: FROM 40' - SURFACE, SPOT 10SX @ 40', CIRC TO SURFACE.
PLUG #4: 10 SX IN MOUSE HOLE, PLUG #5: 15 SX IN RATHOLE.

Name of Plugging Contractor HALLIBURTON SERVICES License No. 5287

Address P.O. Box 1598, LIBERAL, KANSAS 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: PARDEE PRODUCTION Co. ()

STATE OF OKLAHOMA COUNTY OF TULSA, ss.

JAMES L. PARDEE (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct to God.

RECEIVED

KANSAS CORPORATION COMMISSION

(Signature) James Pardee

(Address) 7706 E. 85TH ST., TULSA OK 74133

SUBSCRIBED AND SWORN before me this 20 day of JUNE, 2001

6-28-01

CONSERVATION DIVISION

Susan Mahowkes

Notary Public

My Commission Expires: 1/20/03

OR

Faint, mostly illegible text at the top of the page, possibly a header or introductory paragraph.

0325 X

RECEIVED IN
CONSERVATION DIVISION

DATE: [illegible] TIME: [illegible]
BY: [illegible]

Main body of faint, illegible text, likely the primary content of the document.

RECEIVED
CONSERVATION DIVISION

1964 8 3 1001

CONSERVATION DIVISION

