


15-119-00183-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

WELL PLUGGING RECORD

OR FORMATION PLUGGING RECORD

Strike out upper line
when reporting plug-
ging of formations.



Meade County. Sec. 11 Twp. 35S Rge. (E) 29 (W)
Location as "NE 1/4 NW 1/4 SW 1/4" or footage from lines C-SW-NW
Lease Owner Helmerich & Payne, Inc.
Lease Name R. E. Adams Well No. 1
Office Address 415 Philtower, Tulsa 3, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 11-8 19 46
Application for plugging filed 11-15 19 46
Application for plugging approved 11-16 19 46
Plugging commenced 11-9 19 46
Plugging completed 11-9 19 46
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Mr. Kerr
Producing formation None Depth to top Bottom Total Depth of Well 6,250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
Lensing-Kansas City	Dry	4,305		13-3/8"	475'	None
				9-5/8"	2,776'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.
Mud hole to 300', Dump rock bridge and 15 sacks of cement at 300'
Mud hole to 20', Dump rock bridge and 10 sacks of cement to surface.

11-35-29W
81-44

(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Helmerich & Payne, Inc.
Address 415 Philtower, Tulsa 3, Oklahoma

STATE OF Oklahoma, COUNTY OF Tulsa, ss.
Charles F. King (employee of owner) or (~~owner~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Charles F. King
415 Philtower, Tulsa 3, Oklahoma
(Address)

SUBSCRIBED AND SWORN to before me this 15th day of November 19 46

Walter D. Steffen
Notary Public.
11-16-46

My commission expires 7-22-47

Adms #1
SE/4 E1/4 of Section 11-35S-29E
Meade County, Kansas
R. S. Adams & White Eagle Oil Company

Commenced: September 7, 1946
 Completed: 11-10-46

Sand	0	40 :
Shale and red bed	40	498
Sandy red bed and shale	498	860
Red bed and shale	860	1215
Anhydrite	1215	1256
Shale and red bed	1256	1330
Red bed and shale, shells	1330	1440
Variogated shale	1440	1545
Red bed, shale	1545	1680
Shale and lime	1680	1810
Shale and lime shells	1810	1910
Shale and lime	1910	2180
Lime and shale streaks	2180	2265
Anhydrite	2265	2415
Anhydrite and chert	2415	2430
Shale and anhydrite(broken)	2430	2445
Anhydrite	2445	2485
Anhydrite, cherty	2485	2535
Lime, grey	2535	2570
Lime and shale	2570	2790
Lime	2790	2945
Shale and lime	2945	3160
Shale	3160	3205
Lime	3205	3250
Lime and shale	3250	3490
Shale	3490	4325
Lime	4325	4390
Lime and shale	4390	4635
Lime	4635	4910
Lime, grey and black, hard	4910	4935
Lime	4935	4980
Lime, hard	4980	4985
Lime	4985	5080
Lime and shale	5080	5105
Lime	5105	5135
Lime and shale	5135	5664
Lime	5664	5725
Lime, broken, shale	5725	5780
Shale and lime	5780	5845
Cherty lime	5845	5852
lime	5852	5890
Lime and shale	5890	5910
Lime	5910	6040
Lime and shale	6040	6075
Lime	6075	6171
Shale and lime	6171	6225
Lime	6225	6250
TOTAL DEPTH	6250	

CASING RECORD

13 3/8" O.D. casing set at 498' and cemented with 450 sacks cement.
 9 5/8" O.D. casing set at 2775' and cemented with 1000 sacks cement.

PLUGGING RECORD

Set plug 300 feet below bottom of cellar and cemented with 15 sacks cement.
 Set top plug 20 feet down and cemented with 10 sacks cement.

11 35 29W
 81 44

STATE OF KANSAS)
 COUNTY OF MEADE) ss

I hereby affirm that the above and foregoing is a true and correct copy of the log of the Adams #1 well, located in the southwest quarter of the Northwest quarter of Section 11, Township 35 South, Range 29 East, Meade County, Kansas.

RICHARD E. WYLLIE, Notary Public

Richard E. Wyllie
 Notary Public

Subscribed and sworn to before me, a Notary Public, this 15th day of November, 1946.

Richard E. Wyllie
 Notary Public

My commission expires July 22, 1947.