

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20488-00-01

LEASE NAME Adams

WELL NUMBER I-8

860 Ft. from S Section Line

1967 Ft. from E Section Line

SEC. 8 TWP. 35S RGE. 29 (E) or (W)

COUNTY Meade

Date Well Completed _____

Plugging Commenced 12/21/01

Plugging Completed 12/27/01

RECEIVED

JAN 28 2002

KCC WICHITA

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR EXCO Resources, Inc.

ADDRESS 6500 Greenville Ave. Suite 600 LB 17-Dallas, TX 75206

PHONE#(308) 254-4825 OPERATORS LICENSE NO. 32581

Character of Well Gas

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12/20/01 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation Chester/Morrow Depth to Top 5818' Bottom 6141' T.D. 6382'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8"	1520'	0
				5 1/2"	6343'	=4020'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each set: CIBP @ 5784' with 1 sks cement. Load hole with mud. Spot off pipe at 4020'. 50 sks cement 1530'-1330'. 40 sks cement 500' to 340'. 10 sks cement 40' to 0. With mud spacing each plug.

Name of Plugging Contractor Sargent & Lillard Casing Pulling Inc. License No. 32833

Address PO Box 1450 - Woodward OK 73802 1450


NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EXCO Resources, Inc.

STATE OF Nebraska COUNTY OF Cheyenne, ss.

I, Paul D. Roberts (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) [Signature]

(Address) 2829 Road 111 Sidney, NE 69162



SUBSCRIBED AND SWORN TO before me this 16 day of January, 2002

[Signature]
Notary Public

My Commission Expires: May 7, 2005

OR