

15-119-00168-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bitting Building
Wichita, Kansas

Meade County. Sec. 7 Twp. 35 Rge. 29 (X) (W)

Location as "NE/CNW%SW%" or footage from lines 660' From North & East

Lease Owner Columbian Fuel Corporation

Lease Name H. G. Adams Well No. G-2

Office Address P. O. Drawer 6, Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Gas

Date well completed March 7, 1952

Application for plugging filed August 3 1962

Application for plugging approved August 6 1962


Plugging commenced August 28 1962

Plugging completed September 6 1962

Reason for abandonment of well or producing formation Non-Commercial

If a producing well is abandoned, date of last production August 1962

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Hugh Scott - Liberal, Kansas

Producing formation Morrow Depth to top 5780 Bottom 5794 Total Depth of Well 6237 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Morrow				13 3/8	621	None
				9 5/8	2502	1642
				5 1/2	5839	4562

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Cemented through tubing from 5800' to 5150' with 50 sacks cement.

Filled with mud from 5150' to 600'. Set plug from 600' to 525' with 75 sacks cement.

Filled hole from 525' to 25' with mud.

Placed a 25 foot plug from 25' to 0 with 25 sacks cement.

STATE CORPORATION COMMISSION

SEP 13 1962

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent Casing Pulling Service

Address 121 W. 9th, Liberal, Kansas

STATE OF Kansas COUNTY OF Meade, ss.
Robert B. Gilliam

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert B. Gilliam

P. O. Drawer 6, Liberal, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 11 day of September, 19 62

Colvin Lindsey

Notary Public.

My commission expires November 5, 1962

Hugh E. Scott - Box 1223, Liberal, Kansas
F. J. Bucher - Box 1087, Colorado Springs, Colo.
New York Office
Houston Office
File

United Producing Co. - Box 949,
Liberal, Kansas

15-119-00168-0000

H. G. Adams G. Well No. 2
 NE NE 1/4 Sec. 7-35-29
 Meade County, Kansas
 Columbia Fuel Corporation

Commenced: January 16, 1952
 Completed: March 5, 1952

Asphalt

Set 13-3/4" casing - 634 with 500 sacks
 Set 9-5/8" casing - 2509 with 400 sacks
 Set 5-1/2" casing - 5138 with 300 sacks

Surface Sand & Clay	0	473	Line 1 Shale	403	5058
Clay, Sand & Lime Shells	473	603	Line	505:	5062
Redbed	605	935	Line, shale & porous sandy lime	5062	5074
Redbed, Salt & Sand Shells	935	990	Line & Shale	5074	5100
Redbed, Sand, Shells	990	1210	Line, shale, some chert	5100	5109
Redbed & Lime Shells	1210	1275	Chalky white lime	5109	5115
Anhydrite, Lime, Shells & redbed	1275	1369	Honey-combed sandy lime	5115	5121
Anhydrite & Lime shells	1369	1470	Line & hard lime	5121	5132
Light Blue & red shale	1470	1607	Hard lime	5132	5136
Blue & red shale, Anhydrite	1607	1631	Hard lime & shale	5136	5196
Shale, anhydrite & salt	1631	1700	Line	5196	5179
Shale, Anhydrite & Shells	1700	1700	Sand & lime	5179	5222
Shale & Anhydrite	1700	2133	Line & shale	5222	5293
Anhydrite, Lime Shells & Shale	2133	2159	Cherty lime & shale	5293	5350
Anhydrite, Shells & Shale	2159	2170	Hard lime	5350	5351
Shale & Anhydrite	2170	2402	Cherty lime & shale	5351	5414
Shale, Anhydrite & Salt	2402	2432	Hard lime & shale	5414	5453
Anhydrite, Shale & Lime	2432	2453	Cherty lime & shale	5453	5495
Anhydrite & Shale	2453	2457	Cherty lime	5495	5500
Anhydrite, Cherty lime & shale	2457	2520	Line & shale	5500	5560
Anhydrite & Lime	2520	2533	Shale, lime & sand	5560	5590
Anhydrite & Cherty lime	2533	2561	Line & shale	5590	5672
Shale & Lime	2561	2623	Broken lime & shale	5672	5739
Sandy lime & shale	2623	3051	Shale	5739	6070
Lime, hard	3051	3056	Line & shale	6070	6163
Chalky lime	3056	3061	Shale, lime & chert	6163	6192
Lime & shale	3061	3081	Cherty lime & shale	6192	6209
Lime & shale, Cherty streaks	3081	3154	Line & shale	6209	6237
Lime & shale	3154	3400			
Lime	3400	3456	TOTAL DEPTH	6237	
Sandy, Chalky lime & shale	3456	3462			
Sandy lime & shale	3462	3520			
Lime & shale	3520	3707			
Shale	3707	3900			
Shale & lime	3900	4013			
Shale	4013	4112			
Sandy shale & lime shells	4112	4122			
Shale & lime	4122	4248			
Shale	4248	4277			
Shale & lime shells	4277	4340			
Shale & lime	4340	4601			
Lime & shale, Cherty	4601	4642			
Lime	4642	4650			
Lime & shale	4650	4719			
Lime	4719	4733			
Lime & shale	4733	4749			
Light lime	4749	4773			

(STATE OF KANSAS)

(CITY OF TULSA)

Notarized - 3-17-52

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 6 1962
 CONSERVATION DIVISION
 Wichita, Kansas