

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Meade County, Sec. 6 Twp. 35 Rge. (E) 29 (W)

Location as "NE/CNW/SW" or footage from lines Center NE SE

Lease Owner O. B. Mobley, Jr.

Lease Name H. G. Adams Well No. 1-A

Office Address 1011 Commercial Nat'l Bank Bldg., Shreveport, La.

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed April 19 1968

Application for plugging filed April 23 1968

Application for plugging approved April 26 1968

Plugging commenced May 6 1968

Plugging completed May 8 1968

Reason for abandonment of well or producing formation Not Commercial


If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves

Producing formation St. Louis Depth to top 6358 Bottom 6527 Total Depth of Well 6527 Feet

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above Section Plat

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	1332	8-5/8	1332	None
			6525	4-1/2	6525	3428
St. Louis	Gas	6425	6450			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

- 6250 - 6450 15 sacks cement and 1 sack of Hulls
- 700 - 820 35 sacks cement and 2 sacks of Hulls
- 0 - 45 15 sacks cement
- Steel Plate welded on top of 8-5/8
- Hole was filled with mud.

RECEIVED
STATE CORPORATION COMMISSION
JUN 17 1968
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service
Address Box 506, Liberal, Kansas 67901

STATE OF LOUISIANA, COUNTY OF CADDO, ss. O. G. McDowell

(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) O. G. McDowell

1011 Commercial Nat'l Bank Bldg., Shreveport, La. (Address)

SUBSCRIBED AND SWORN TO before me this 14th day of June 1968

My commission expires Clarence J. Edwards, Notary Public in and for Caddo Parish, State of Louisiana. My Commission is for life.

Notary Public signature

WELL LOG

COMPANY O. B. MOBLEY, JR.

SEC. 6-T35S-R29W

FARM H. G. ADAMS NO. 1-"A"

LOC. 50'S-C-NE-SE

TOTAL DEPTH 6525'
6527' LTD

COUNTY Meade


COMM. March 11, 1968 COMP. March 28, 1968

CONTRACTOR

CASING

8 5/8" @ 1332' w/650 sx.

4 1/2" @6525' w/325 sx.



ELEVATION 2491 Gd.

PRODUCTION Gas

FIGURES INDICATE BOTTOM OF FORMATIONS

725'	Surface Sand & Red Bed
1332'	Sand - Red Bed
1610'	Anhydrite - Red Bed
2260'	Red Bed - Shale & Shells
2490'	Lime - Shale
2617'	Shale - Lime
3600'	Lime - Shale
3810'	Shale - Lime
4010'	Lime - Shale
4335'	Shale
4461'	Shale - Lime
4615'	Lime - Shale
4695'	Lime
4990'	Lime - Shale
5065'	Lime
5240'	Lime - Shale
5690'	Lime
5940'	Lime - Shale
5943'	Lime
6140'	Shale - Lime
6282'	Lime - Shale
6525' T.D.	Lime

RECEIVED
STATE CORPORATION COMMISSION
APR 26 1968
CONSERVATION DIVISION
Wichita, Kansas

State of Kansas }
County of Sedgwick } ss

I, C. Robert Buford, President of Zenith Drilling Corporation, Inc.

upon oath state the above and foregoing is a true and correct copy of the log of the H. G. Adams #1-"A" well.

C. Robert Buford
C. Robert Buford

Subscribed and sworn to before me this 1st day of April, 1968.

My Commission Expires August 15, 1971.

Myrna D. Murphy
Myrna D. Murphy NOTARY PUBLIC

