

STATE OF KANSAS
STATE CORPORATION COMMISSION
130 S. Market, Room 2078
Wichita, KS 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20786-00-00

LEASE NAME Adams Ranch

WELL NUMBER F-35

2300 Ft. from S Section Line

1200 Ft. from E Section Line

SEC. 4 TWP. 35 SRGE. 29 (E) or (W)

COUNTY Meade

Date Well Completed _____

Plugging Commenced 12/18/01

Plugging Completed 12/20/01

RECEIVED

JAN 25 2002

KCC WICHITA

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR EXCO Resources, Inc

ADDRESS 6500 Greenville Ave, Suite 600 LB17-Dallas TX 75206

PHONE#(308) 254-4825 OPERATORS LICENSE NO. 32581

Character of Well Oil

(Oil, Gas, D&A, SMD, Input, Water Supply Well)

The plugging proposal was approved on 12/17/01 (date)

by Steve Middleton (KCC District Agent's Name).

Is ACO-1 filed? yes if not, is well log attached? _____

Producing Formation _____ Depth to Top 4992' Bottom 5012' T.D. 5185'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				20"	70'	0
				8 5/8"	1537'	0
				5 1/2"	5181'	3230'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from ___ feet to ___ feet each set. CIBP @ 4946' with 1 sk cement. Load hole with mud. Shoot off pipe at 3230' 50 sks cement 1560' to 1360' 40 sks cement 500' to 340' 10 sks cement 40' to 0. With mud spacing each plug

Name of Plugging Contractor Sargent & Lillard Casing Pulling Inc License No. 32833


Address PO Box 1450 - Woodward, OK 73802-1450

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: EXCO Resources, Inc.

STATE OF Nebraska COUNTY OF Cheyenne, ss.

I, Paul D. Roberts (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained and the log of the above-described well as filed the the same are true and correct, so help me God.

(Signature) Paul D. Roberts



(Address) 2829 Road 111, Sidney NE 69162

SUBSCRIBED AND SWORN TO before me this 16 day of January, 192002

Debra C. Terry
Notary Public

My Commission Expires: May 7, 2005

OR