

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Bldg.
Wichita, Kansas 67202

Form CP-4
Rev. 12-15-80

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit

COUNTY Meade SEC. 3 TWP. 35S RGE. 29W E/W
Location as in quarters or footage from lines:
1250' FNL 1250' FEL

Lease Owner R. Clay Underwood
Lease Name H.G. Adams 111 Well No. F - 9
Office Address Suite 420 Oil & Gas Bldg. Wichita Falls, Texas
Character of Well (Completed as Oil, Gas or Dry Hole): Gas
Date Well Completed 8/23/77
Application for plugging filed September 21, 1981
Plugging commenced 9-28-81
Plugging completed 10-1 -81
Reason for abandonment of well or producing formation No longer productive

Locate Well
correctly on above
Section Platt.

Was permission obtained from the Conservation Division or it's
Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Paul Luthi
Producing formation _____ Depth to top _____ bottom T.D. 6300
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
				8 5/8	1528	none
				5 1/2	6250	2631

Describe in detail the manner in which the well was plugged, indicating where the mud
fluid was placed and the method or methods used in introducing it into the hold. If cement
or other plugs were used, state the character of same and depth placed, from _____ feet
to _____ feet for each plug set.

Pump 30 sks. of cement from 4500 to 4200
Pump 50 sks. of cement from 1520 to 1420
Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Box 506 Liberal, Kansas 67901

STATE OF TEXAS COUNTY OF WICHITA, ss.
R. CLAY UNDERWOOD (~~employee of owner~~) or (owner or operator) of the

above-described well, being first duly sworn on oath, says: That I have knowledge of the
facts, statements, and matters herein contained and the log of the above-described well as
filed and that the same are true and correct. So help me God.

(Signature) [Signature]
Suite 420 Oil & Gas Bldg.
(Address)
Wichita Falls, Texas 76301

SUBSCRIBED AND SWORN TO before me this 10 day of October, 19 81

[Signature] Betty Wolford
In and For Wichita Co., Tex. Notary Public

My Commission expires: June 3, 1985

RECEIVED
STATE CORPORATION COMMISSION

NOV 20 1981

CONSERVATION DIVISION
Wichita, Kansas

R. CLAY UNDERWOOD

3
H. G. ADAMS IN WELL NO. 9F
 Meade County, Kansas

OPERATIONS COMMENCED: 3/4/77

OPERATIONS COMPLETED: 3/25/77

Drillers Log

3/4/77	0 - 98	Sand
3/5/77	98 - 1509	Sand, Red Bed, Anhydrite
3/6/77	1509 - 1569	Anhydrite
3/7/77	1569 - 2435	Anhydrite and Shale
3/8/77	2435 - 2912	Anhydrite, Shale and Lime
3/9/77	2912 - 3496	Lime
3/10/77	3496 - 3954	Lime
3/11/77	3954 - 4405	Lime
3/12/77	4405 - 4412	Toronto
3/13/77	4412 - 4752	Toronto and Lime
3/14/77	4752 - 5012	Lansing
3/15/77	5012 - 5117	Lansing
3/16/77	5117 - 5246	Lansing
3/17/77	5246 - 5430	Marmaton
3/18/77	5430 - 5602	Marmaton
3/19/77	5602 - 5783	Marmaton
3/20/77	5783 - 5988	Morrow, Chester
3/21/77	5988 - 6050	Chester
3/22/77	6050 - 6185	Chester
3/24/77	6185 - 6279	Lime, Shale, Chester
3/25/77	6279 - 6300	Chester

Casing Record

3/6/77

Ran 37 joints 8 5/8" K55, 24# casing.
 Cemented with 600 sacks 2%cc. Followed
 with 150 sacks Class H., 3% c.c.

3/27/77

Ran 166 joints 5 1/2" 15.5# K-55 casing. Cemented
 with 450 sacks Light Weight 7 1/2# Kolite, 18%
 salt saturated.

5988

RECEIVED
 STATE CORPORATION COMMISSION

SEP - 1 1981

CONSERVATION DIVISION
 Wichita, Kansas