

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-119-20,218-0000

LEASE NAME ADAMS

WELL NUMBER #2-2

1000' Ft. from S Section Line

3960' Ft. from E Section Line

SEC. 2 TWP. 35 RGE. 29 (E) or (W)

COUNTY Meade

Date Well Completed 3/12/76

Plugging Commenced 8/8/88

Plugging Completed 8/8/88

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR MESA OPERATING LIMITED PARTNERSHIP

ADDRESS P.O. BOX 2009, AMARILLO, TEXAS 79189

PHONE# (806) 378-1000 OPERATORS LICENSE NO. 04824

Character of Well oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City - Richard Lacey

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Chester Depth to Top 5772' Bottom 5782' T.D. 6100'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
5772'-82'	oil, water			8 5/8"	1447'	none
				2 7/8"	6060'	2631'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Notified R. Lacey 8/8/88. MI plugging unit, pumped 25 BFW down tbg. Made sinker bar run to 3000'. Shot tubing @ 2631' WLM. Circ 25 bbls gel wtr. mixed 30 sx cement, displace to 2631'. POH. set cement plug from 1470'-1397'; Set cement plug from 700'-650'; set cement plug from 40' to surface. Witnessed by Glenn Beibus w/KCC. Well P&A 8/8/88.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 06547

Address 620 So. Lincoln, Liberal, Kansas 67901

STATE OF TEXAS COUNTY OF POTTER, ss.

Carolyn L. Cummings


(Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Carolyn Cummings

(Address) P.O. Box 2009, Amarillo, TX 79189

SUBSCRIBED AND SWORN TO before me this 10th day of August, 1988

Dwaina Pitts
Notary Public



RECEIVED
STATE CORPORATION COMMISSION
AUG 12 1988

CONSERVATION DIVISION
Wichita, Kansas
Commission Expires:

WELL LOG

15-119-20218-0000

COMPANY Mesa Petroleum Co.

RECEIVED

SEC. 2 T. 35S R. 29W
 LOC. 1000' FSL & 1320' FWL

FARM Adams

NO. #2-2

MAR 17 1976

RIG. NO. 5

AMA. PROD.

COUNTY Meade

TOTAL DEPTH

KANSAS

COMM. 2-26-76

COMP. 3-12-76

CONTRACTOR Rains & Williamson Oil Co., Inc.

CASINO

20	10	5/8" @ 1447' w/600 sx Halco Lite	ELEVATION	
15	6	2% cc & 200 sx TYPE H, 3% cc	PRODUCTION	Oil
12	5	2-7/8" tubing @ 6100' w/200 sx, 50/50 pos, 12½ Gil,		
10		10% salt, CFR2-1%.		

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand & Red Bed	397
Red Bed	997
Surface	1260
Red Bed & Anhydrite	1447
Red Bed & Clay	1715
Red Bed & Sand	2105
Sand & Shale	2300
Shale & Shells	2417
Shale	2780
Shale & Lime	3084
Lime & Shale	3285
Dolo	3513
Lime	3655
Lime & Shale	3865
Shale	4307
Lime & Shale	4490
Shale & Lime	4837
Lime & Shale	5110
Shale & Lime	5210
Lime & Shale	5420
Shale & Lime	5520
Lime & Shale	5785
Shale & Lime	5882
Lime & Shale	6075
Shale & Lime	6100
<u>Rotary Total Depth</u>	<u>6100</u>

RECEIVED
 STATE CORPORATION COMMISSION

JUN 16 1988

CONSERVATION DIVISION
 Wichita, Kansas