


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

MEADE County. Sec. 13 Twp. 35S Rge. (E) 28 (W)
C W 1/2 NE 1/4

Location as "NE/CNWxSWx" or footage from lines
Lease Owner KING RESOURCES COMPANY
Lease Name E. MEYERS Well No. 1-13
Office Address 100 PARK AVENUE BLDG., OKLA. CITY, OKLA. 73102
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE
Date well completed MARCH 26, 19 68
Application for plugging filed (PHONE 3/26/68) MARCH 29, 19 68
Application for plugging approved MARCH 26, 19 68
Plugging commenced MARCH 26, 19 68
Plugging completed MARCH 26, 19 68
Reason for abandonment of well or producing formation



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well EDGAR EYES
Producing formation Depth to top Bottom Total Depth of Well 6465 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	692'	8-5/8"	692'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

FILLED HOLE WITH HEAVY MUD TO 692 FEET. SET FIRST PLUG @ 692' WITH 35 SACKS CEMENT.
FILLED HOLE WITH HEAVY MUD TO 45 FEET. SET SECOND PLUG @ 45' WITH 15 SACKS CEMENT.
PLUGGED THROUGH DRILL PIPE WITH HALLIBURTON PUMP TRUCK. JOB COMPLETE @ 9:45 PM,
MARCH 26, 1968.

RECEIVED
STATE CORPORATION COMMISSION
APR 1 1968
CONSERVATION DIVISION
Wichita, Kansas


(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor GABBERT-JONES, INC.
Address 830 SUTTON PLACE, WICHITA, KANSAS 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
E. E. HALL (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]
830 SUTTON PLACE, WICHITA, KANSAS 67202
(Address)

SUBSCRIBED AND SWORN TO before me this 29 day of MARCH, 19 68



[Signature]
BARBARA J. LAYTON Notary Public.

My Commission Expires Feb. 1, 1972

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

E. MEYERS #1-13
C W $\frac{1}{2}$ NE $\frac{1}{4}$ SECTION 13-35S-28W
MEADE COUNTY, KANSAS

COMMENCED: MARCH 7, 1968
COMPLETED: MARCH 26, 1968

OPERATOR - KING RESOURCES COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0	320	SAND AND CLAY	RAN 17 JOINTS 8-5/8" CASING, SET @ 692' w/300 SACKS CEMENT.
320	698	RED BED AND SAND	
698	1335	RED BED, SAND AND SHALE	
1335	1780	SHALE AND SHELLS	
1780	2545	SHALE AND LIME	
2545	3302	LIME	
3302	3320	LIME AND SHALE	
3320	3425	LIME	
3425	4599	SHALE AND LIME	
4599	5866	LIME	
5866	6086	LIME AND SHALE	
6086	6120	LIME	
6120	6210	LIME AND SHALE	
6210	6240	LIME	
6240	6465	LIME AND SHALE	
6465	TD		DRY AND ABANDONED.

RECEIVED
STATE CORPORATION COMMISSION
APR 1 1968
CONSERVATION DIVISION
Wichita, Kansas

I, E. E. HALL, CERTIFY THIS IS A CORRECT COPY OF THE DRILLERS' LOG FOR THE WELL DRILLED IN THE C W $\frac{1}{2}$ NE $\frac{1}{4}$ SECTION 13-35S-28W, MEADE COUNTY, KANSAS, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

E. E. Hall
E. E. HALL

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 29TH DAY OF MARCH, 1968, PERSONALLY APPEARED E. E. HALL, TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS WHEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

Barbara J. Layton
BARBARA J. LAYTON, NOTARY PUBLIC

My COMMISSION EXPIRES FEBRUARY 1, 1972.

