

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

15-129-10401-0000
FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM

(File One Copy)

15-129-10401-00-00

API NUMBER

3/9/56

(of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) ISU WELL NO. 27 WELL LOCATION C NE NW COUNTY Morton

SEC. 20 TWP. 34S RGE. 43 (E) or (W) TOTAL DEPTH 4265 PLUG BACK TO 4090 w/CIBP
2/25/83

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8 5/8 SET AT 1119 CEMENTED WITH 600 SACKS

CASING SIZE 5 1/2 SET AT 4265 CEMENTED WITH 200 SACKS

DV TOOL

3106

400

PERFORATED AT 4192-4212

CONDITION OF WELL: GOOD _____ POOR _____ CASING LEAK JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL Proposed plugging method. Using tbg, top CIBP @ 4090' w/20 sxs cmt. Shoot off csg @ free point. Spot 25 sxs cmt @ cut off point, 50 sxs from 1250'-1000', 35 sxs from 650'-480', & 10 sxs from 50'-0'. Spot 9 PPG mud between cmt plgs in surface pipe. Cut off csg 3' below ground level. Weld on steel plate. Cmt type will be 60/40 poz w/6% gel. Restore location to Forest Service specifications.

(If additional space is needed use back of form)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? NA IS ACO-1 FILED? Physical productivity report filed.
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN Upon approval.

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin B. Johnson

PHONE # (316) 697-2188

ADDRESS P. O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargents Casing Pulling Service

LICENSE NO. 6547

ADDRESS 620 S. Lincoln, Liberal, Kansas 67901

PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT

SIGNED: Daudu Kappo for M. L. Pease
(Operator or Agent)

M. L. Pease, Division Production Manager

DATE: 8/2/89

①

15-129-10401-0000

ANADARKO PETROLEUM CORPORATION 2330 NORTH KANSAS AVE. • P.O. BOX 351 • LIBERAL, KANSAS 67905-0351



August 2, 1989

Kansas Corporation Commission
200 Colorado Derby Building
202 West First Street
Wichita, Kansas 67202-1286

Attention: Denise Anderson

Re: Well Plugging Application Form (CP-1)
Interstate Unit Nos. 14, 26, 27, and 33
Sections 17 and 20-34S-43W
Morton County, Kansas
Interstate Purdy Morrow Unit

Dear Ms. Anderson:

Attached for your approval are well plugging applications (KCC Form No. CP-1) for the subject wells. These wells are temporarily abandoned or shut in and have no further utility to the unit.

Upon your approval Anadarko will begin plugging operations. If there are any questions, please contact the above office.

Very truly yours,

David Kapple for M. Pease

M. L. Pease
Division Production Manager
TAW/sh

Attachments

cc: Well Files w/appropriate attachments
Unit Correspondence File
Per Burchardt - Denver

RECEIVED
STATE CORPORATION COMMISSION

AUG - 3 1989

CONSERVATION DIVISION
Wichita, Kansas

State of Kansas



Kansas Corporation Commission

MIKE HAYDEN GOVERNOR
KEITH R. HENLEY CHAIRMAN
RICH KOWALEWSKI COMMISSIONER
MARGALEE WRIGHT COMMISSIONER
JUDITH MCCONNELL EXECUTIVE DIRECTOR
FRANK A. CARO, JR. GENERAL COUNSEL

CONSERVATION DIVISION
SHARI FEIST ALBRECHT, DIRECTOR
200 Colorado Derby Bldg.
202 W. 1st Street
Wichita, KS 67202-1286
(316) 263-3238

THIS NOTICE

NOV 7 1989

EXPIRES
August 7, 1989

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION

Anadarko Petroleum Corporation
P.O. Box 351
Liberal, KS 67905-0351

ISU 27
C NE NW
20-34-43W
Morton County

Gentlemen:

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging. Please contact the district office to review your proposed plugging method at least five (5) days before plugging the well.

It has recently come to my attention that the form CP-1 has been filed by operators other than the owner or operator of the well and without the consent of the owner or operator. The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well. The CP-1 is simply reviewed to determine compliance with plugging rules and regulations.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist Albrecht

Shari Feist Albrecht
Director

District: #1 304 W. McArtor
Dodge City, KS 67801
(316) 225-6760