

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

RECEIVED CP-1
KANSAS CORPORATION COMMISSION
02/92

JAN 18 1995

WELL PLUGGING APPLICATION FORM
(PLEASE TYPE FORM and File ONE Copy)

CONSERVATION DIVISION
WICHITA, KS

API # 15-129-20,454-0000 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR ANADARKO PETROLEUM CORPORATION KCC LICENSE # 4549
(owner/company name) (operator's)

ADDRESS P.O. BOX 351 CITY LIBERAL

STATE KANSAS ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE INTERSTATE "F" WELL# 3 SEC. 20 T. 34S R. 43 (XXXX West)

W/2- SW - NE - SE SPOT LOCATION/QQQQ COUNTY MORTON

1650 FEET (in exact footage) FROM (S)X (circle one) LINE OF SECTION (NOT Lease Line)

1250 FEET (in exact footage) FROM (E)X (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL GAS WELL D&A SWD/ENHR WELL DOCKET# _____

CONDUCTOR CASING SIZE _____ SET AT _____ CEMENTED WITH _____ SACKS

SURFACE CASING SIZE 8 5/8" SET AT 350' CEMENTED WITH 350 SACKS

PRODUCTION CASING SIZE 4 1/2" SET AT 1330' CEMENTED WITH 500 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 1179-88', 1194-1210'

ELEVATION 3476'/3481' T.D. 1330' PBDT 1324' ANHYDRITE DEPTH _____
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD POOR CASING LEAK JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIRU CSG PULLERS.TOH WITH RODS & PUMP LAYING DOWN. LOAD HOLE W/9 PPG MUD AND ESTABLISH CIRCULATION DOWN 2-3/8" TBG.MIX AND SPOT 2 SXS HULLS AND 20 SXS CLASS H CMT(YLD 1.06cuft/sk) FROM 1324-1090'.DISPLACE CMT W/190 GALS WTR.TOH W/TBG TO 450'.SPOT 15 SXS CMT FROM 450-270'.DISPLACE CMT W/80 GALS WTR.TOH W/TBG.SPOT 5 SXS CMT 40-4'.CUT OFF 4-1/2" & 8-5/8" CSG 4' BELOW GROUND LEVEL AND CAP.PERMANENTLY INSCRIBE THE DATE OF PLUGGING AND WELL NAME ON TOP OF CAP.RESTORE LOCATION AND SUBMIT FINAL RECLAMATION NOTICE TO THE BLM.

(If additional space is needed attach separate page)

DRILLERS

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? - IS ACO-1 FILED? LOG FILED

If not explain why? _____

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

MARVIN JOHNSON PHONE# (316) 697-2188

ADDRESS P.O. DRAWER X City/State ELKHART, KANSAS 67951

PLUGGING CONTRACTOR SARGENT & HORTON PLUGGING, INC. KCC LICENSE # 31151
(company name) (contractor's)

ADDRESS RT 1, BOX 49BA, TYRONE, OK 73951-9731 PHONE # (405) 854-6515

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) UPON APPROVAL

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 1-13-95 AUTHORIZED OPERATOR/AGENT: J.M. ASHTON (signature) DIV. PROD. MGR.

8/95

1/95



Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Rachel C. Lipman, Commissioner
Judith McConnell, Executive Director

NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

January 19, 1995

Anadarko Petroleum Corporation
P O Box 351
Liberal KS 67905-0351

Interstate "F" #3
API 15-129-20,454
1650 FSL 1250 FEL
Sec. 20-34S-43W
Morton County

Dear Marvin Johnson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

David P. Williams
Production Supervisor

District: #1
304 W. McArtor
Dodge City KS 67801
(316) 225-6760