

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

15-129-10404-0000

**WELL PLUGGING APPLICATION FORM**  
(PLEASE TYPE FORM and File ONE Copy)

API # 7-19-55 Spud Date (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR Anadarko Petroleum Corporation KCC LICENSE # 4549  
(owner/company name) (operator's)

ADDRESS P. O. Box 351 CITY Liberal

STATE Kansas ZIP CODE 67905-0351 CONTACT PHONE # (316) 624-6253

LEASE Interstate Unit WELL # 45 SEC. 20 T. 34S R. 43 (East West)

1320 FEET (in exact footage) FROM (S)/N (circle one) LINE OF SECTION (NOT Lease Line)  
1320 FEET (in exact footage) FROM (E)/W (circle one) LINE OF SECTION (NOT Lease Line)

Check One: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET# \_\_\_\_\_

CONDUCTOR CASING SIZE 13-3/8" SET AT 80' CEMENTED WITH 125 SACKS  
SURFACE CASING SIZE 8-5/8" SET AT 1119' CEMENTED WITH 700 SACKS  
PRODUCTION CASING SIZE 5-1/2" SET AT 4520' CEMENTED WITH 200 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4152-4166', CIBP @ 4052'

ELEVATION 3472' T.D. 4755' PSTD 4172' ANHYDRITE DEPTH \_\_\_\_\_  
(G.L./K.B.) (Stone Corral Formation)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING TIH w/1-1/4" tbg. Circulate hole w/9 ppg mud. Spot 15 sxs of Class H from 4172-4072'. TOH w/1-1/4" tbg. Pull free point and cut off 5-1/2" csg. Spot 25 sxs cmt @ cut off depth. Spot 60 sxs cmt @ 1219-1019' Spot 35 sxs cmt @ 650-550'. Spot 15 sxs cmt @ 53-3'. Cut off 8-5/8" csg 3' below ground level and cap. Restore location and contact USFS.

(If additional space is needed, attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? - IS ACO-1 FILED? Filed

If not explain why? \_\_\_\_\_

APR 28 1994

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin Johnson PHONE # (316) 697-2188

ADDRESS P. O. Drawer X City/State Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargent & Horton Plugging, Inc. KCC LICENSE # 31151  
(company name) (contractor's)

ADDRESS Rt 1 Box 49BA, Tyrone, OK 73951-9731 PHONE # (405) 854-6575

PROPOSED DATE AND HOUR OF PLUGGING (If Known?) Upon Approval

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 4-26-94 AUTHORIZED OPERATOR/AGENT: [Signature]  
(signature)

J. L. Ashton, Division Production Manager



Kansas Corporation Commission

Joan Finney, Governor    Jim Robinson, Chairman    F.S. Jack Alexander, Commissioner    Rachel C. Lipman, Commissioner  
Judith McConnell, Executive Director    Brian Moline, General Counsel

**NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)**

April 28, 1994

Anadarko Petroleum Corporation  
P O Box 351  
Liberal KS 67905-0351

Interstate Unit #45  
API 15-N/A <sup>1320</sup>  
~~1980 FSL~~ ~~1980 FEL~~  
Sec. 20-34S-43W  
Morton County

Dear Marvin Johnson,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,  
  
David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City KS 67801  
(316) 225-6760