

15-129-10408-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
CONSERVATION DIVISION
200 Colorado Derby Building
Wichita, Kansas 67202

FORM CP-1
Rev. 6/4/84

WELL PLUGGING APPLICATION FORM

(File One Copy)

API NUMBER 15-129-10408-00-00
11/11/55 (of this well)

(This must be listed; if no API# was issued, please note drilling completion date.)

LEASE OPERATOR Anadarko Petroleum Corporation OPERATORS LICENSE NO. 4549

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351 PHONE # (316) 624-6253

LEASE (FARM) *INTERSTATE UNIT WELL NO. 34 WELL LOCATION C SE NW COUNTY Morton

SEC. 20 TWP. 34S RGE. 43 (E) or (W) TOTAL DEPTH 4552 PLUG BACK TD 4060 w/CIBP

Check One:

OIL WELL GAS WELL _____ D & A _____ SWD or INJ WELL _____ DOCKET NO. _____

SURFACE CASING SIZE 8-5/8 SET AT 1193 CEMENTED WITH 600 SACKS

CASING SIZE 5-1/2 SET AT 4300 CEMENTED WITH 250 SACKS
DV TOOL 3214 400 sacks

PERFORATED AT 4172-98

CONDITION OF WELL: GOOD _____ POOR CASING LEAK _____ JUNK IN HOLE _____

OPERATOR'S SUGGESTED METHOD OF PLUGGING THIS WELL CIBP set @ 4060. Dump 20 sxs cmt on top. Load

hole w/lease water. Shoot off csg at freepoint. Spot 60/40 Poz w/6% gel plugs as follows: 30

sxs at casing cut, 40 sxs from 1350-1150, 35 sxs from 650-480, and 10 sxs from 50-0'. Spot 9 pp

(If additional space is needed use back of form) (over)
Drillers Log Physical

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? Attached IS ACO-1 FILED? Productivity Reports Filed
(If not, explain)

DATE AND HOUR PLUGGING IS DESIRED TO BEGIN ASAP

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et seq AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

Marvin B. Johnson PHONE # (316) 697-2188

ADDRESS P. O. Drawer X, Elkhart, Kansas 67950

PLUGGING CONTRACTOR Sargents Casing Pulling Service LICENSE NO. 6547

ADDRESS 620 South Lincoln, Liberal, Kansas 67901 PHONE # (316) 624-7455

PAYMENT WILL BE GUARANTEED BY OPERATOR OR AGENT SIGNED: M. L. Pease RECEIVED
STATE CORPORATION COMMISSION

*Formerly J. M. Huber Corporation
Block "A" No.5

(Operator or Agent)
M. L. Pease, Division 599241007 Manager

DATE: 9/23/87 9-24-87

CONSERVATION DIVISION
Wichita, Kansas

mud between each plug located in the surface casing. Cut off casing below ground level and cap well. Restore location.



Mike Hayden
Keith R. Henley
Rich Kowalewski
Margalee Wright
Judith A. McConnell

Governor
Chairman
Commissioner
Commissioner
Executive Director

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
200 Colorado Derby Building
202 West 1st Street
WICHITA, KANSAS 67202-1286

THIS NOTICE

DEG 25 '87

EXPIRES

September 25, 1987

WELL PLUGGING NOTICE

Interstate Unit #34
C SE NW
Sec. 20-34S-43W
Morton County

Anadarko Petroleum Corporation
P. O. Box 351
Liberal, KS 67905-0351

Gentlemen:

This is your notice to plug the above subject well in accordance with the Rules and Regulations of the State Corporation Commission.

Please contact the district office listed below to review your suggested method of plugging five days prior to plugging the well (KAR-82-3-113).

This notice is void after ninety (90) days from the above date.

Sincerely,

Shari Feist
Director
State Corporation Commission

DISTRICT #1 302 W. McArtor, Dodge City, KS 67801 (316) 225-6760