

LEASE NAME W. Fox

WELL NUMBER 1

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div. office within 30 days.

E/2 SW SE Ft. from S Section Line

 Ft. from E Section Line

LEASE OPERATOR William Gruenerwald & Ass., Inc

SEC. 3 TWP. 35S RGE. 30W (E) or (W)

ADDRESS P.O. Box 909, Colorado Springs, Co. 80901

COUNTY Meade

PHONE (719) 635-2575 OPERATORS LICENSE NO. 08685

Date Well Completed

Character of Well Oil

Plugging Commenced 12-27-89

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 12-29-89

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Glenn Barlow

Is ACO-1 filed? If not, is well log attached?

Producing Formation Depth to Top Bottom T.O. 6317

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1370	0
				5 1/2	6317	2605

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

- Pump 25 sks. of cement from 6249 to 6000
- Pump 50 sks. of cement from 1400 to 1200
- Pump 40 sks. of cement from 600 to 500
- Put 10 sks. of cement from 40 to 0 Cut off & cap 8 5/8 3' below ground level

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling service License No. 6547

Address P.O. Box 506 Liberal, Kansas 67905-0506

STATE OF Kansas COUNTY OF Seward, ss.

 (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters contained and the log of the above-described well as filed that the same are true and correct, so help me God.

CONSERVATION DIVISION
 Wichita, Kansas
 4-11-90

(Signature) [Signature]
 (Address) 1039 N. SHERMAN.

SUBSCRIBED AND SWORN TO before me this 10th day of April, 1990

Kathryn A. Rowley
 Notary Public

My Commission Expires: 8-1-92



15-119-10249-0000

WELL LOG

COMPANY William Gruenerwald & Associates, Inc.

SEC. 3 T. 35S R. 30W

FARM Fox NO. 1

LOC. SW SE

TOTAL DEPTH 6318'

COUNTY Meade

COMM. 10-2-66 COMP. 10-18-66

CONTRACTOR Garvey Drilling Company

CASING 8 5/8" @ 1370' w/800 SX
 6 1/2" @ 6318' w/300 SX

ELEVATION

PRODUCTION

FIGURES INDICATE BOTTOM OF FORMATIONS

- 1220' Red Bed
- 1370' Red Bed and Anhydrite
- 1695' Anhydrite and Shale
- 2185' Shale and Lime
- 2870' Lime and Shale
- 2873' Lime
- 4450' Lime and Shale
- 4600' Lime and Shale and Chalk Streaks
- 4818' Lime and Shale
- 6318' Lime
- 6318' RTD

RECEIVED
STATE CORPORATION COMMISSION

DEC 28 1969

CONSERVATION DIVISION
Wichita, Kansas