

STATE OF KANSAS
STATE CORPORATION COMMISSION


Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

Meade County, Sec. 3 Twp. 35 Rge. 30 (E) (W) X

Location as "NE/CNW/SE" or footage from lines C NE SE
Lease Owner Bulldog Pipe & Supply- S & S Pipe & Supply
Lease Name Fox Well No. 4
Office Address 309 Mayo Building Tulsa, Oklahoma
Character of Well (completed as Oil, Gas or Dry Hole) _____
Date well completed _____ 19____
Application for plugging filed _____ 19____
Application for plugging approved _____ 19____
Plugging commenced 6-18-68 _____ 19____
Plugging completed 6-22-68 _____ 19____
Reason for abandonment of well or producing formation _____



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production _____ 19____
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Edgar J. Eves
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5915 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	1376	None
				5 1/2	None	2813

RECEIVED
STATE CORPORATION COMMISSION
JUL 9 1968
CONSERVATION DIVISION
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Moved in.

Sanded to 5900'. Dumped 5 sacks of cement. Breaking out cement.
Cleaned out cellar. Rigged up. Working pipe.

Working pipe. Shot pipe at 4800' - 4500' - 4000' - 3700' and 3510'.

Working pipe. Shot pipe at 3300' - 3000' - 2900' - 2800' and 2700'.
Pulling pipe.

Plugging well. Set rock bridge at 700'. Dumped 35 sacks of cement.
Mudded hole to 45' rock bridge. Capped well with 15 sacks of cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling, Inc.
Address P. O. Box 221 Great Bend, Kansas 67530

STATE OF Kansas COUNTY OF Barton, ss.
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes
P. O. Box 221 Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 8 day of July, 19 68.

My commission expires May 27, 1969

Notary Public.

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

15-119-10347-0000


COPY

Company. THOMAS & BREWER
Farm. FOX No. 4

SEC. 3 T. 35 R. 30W
NE SE NE

Total Depth. 5963'
Comm. 3-8-60 Comp. 4-3-60
Shot or Treated.
Contractor. Earl F. Wakefield
Issued. 5-12-62

County Meade
KANSAS



Elevation. 2547' DF

Production. 4,000,000 CFG

CASING:

8 5/8" 1376'
5 1/2" 5962' - 160 Sink

Figures Indicate Bottom of Formations

clay, sand clay	258
red bed	555
red bed & shale	1055
red bed & shale	1352
Anhydrite	1374
Anhydrite & shale	1480
shale	1976
shale & shells	2235
Anhydrite & shale	2481
Anhydrite & lime	2573
lime, Anhydrite	2651
lime	2766
lime & shale	2871
lime, sand & shale	2951
lime	3050
lime, shale & chalk	3180
lime	3265
lime & chalk	3650
lime & sand	3796
lime, chalk	3877
lime & shale	4040
shale, lime	4165
lime, shale	4250
shale & shells	4344
lime & shale	4502
lime	4525
lime & shale	4655
shale, lime	4658
shale	4894
lime & shale	4991
lime	5020
lime, shale & chalk	5114
chalk lime & shale	5165
shale	5172
shale & lime	5250
lime & shale	5307
lime	5327
lime & some chert	5392
lime, shale	5424
lime	5691
lime & shale	5800
lime	5853
lime & sand	5918
lime & shale	5963
Total Depth	

TOPS: SCOUT	
Council Grove	3142
Heebner	4373
Toronto	4409
Lansing	4538
Marmaton	5218
Cherokee	5400
Atoka	5626
Morrow	5780
Chester	5915

RECEIVED
STATE GEOLOGICAL SURVEY
JUN 5 1962
CONSERVATION DIVISION
Wichita, Kansas