

RECEIVED  
STATE CORPORATION COMMISSION

SEP 26 1974


CONSERVATION DIVISION  
Wichita, Kansas

Form CP-4

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
P. O. Box 17027  
Wichita, Kansas 67217

WELL PLUGGING RECORD



Locate well correctly on above  
Section Plat

Meade County, Sec. 2 Twp. 35 Rge. 30 (E) (W) X  
Location as "NE/CNW/SW" or footage from lines C SW SE  
Lease Owner Ralph (Red) Clark  
Lease Name Adams Ranch Well No. 1  
Office Address Box 564 Liberal, Kansas 67901  
Character of Well (completed as Oil, Gas or Dry Hole) Gas & Oil  
Date well completed Sept. 19 72  
Application for plugging filed \_\_\_\_\_ 19 \_\_\_\_\_  
Application for plugging approved August 23 19 74  
Plugging commenced \_\_\_\_\_ 19 \_\_\_\_\_  
Plugging completed August 27 19 74  
Reason for abandonment of well or producing formation Depleted

If a producing well is abandoned, date of last production March 19 74  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ed Eves  
Producing formation Morrow Depth to top. 5764' Bottom 5842' Total Depth of Well 6400'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT     | FROM | TO   | SIZE  | PUT IN | PULLED OUT |
|-----------|-------------|------|------|-------|--------|------------|
| St. Louis | Oil & water | 6230 | 6320 | 8 5/8 | 1510   | none       |
| Morrow    | Gas & Oil   | 5764 | 5842 | 5 1/2 | 6388   | 4407       |
|           |             |      |      |       |        |            |
|           |             |      |      |       |        |            |
|           |             |      |      |       |        |            |
|           |             |      |      |       |        |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Pump 20 sks. of cement @ 5764' To 5550  
Pump 30 sks. of cement @ 900 to 800  
Put 10 sks. of cement @ 140 to 0

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Sargents Casing Pulling Service Kansas No. 511  
Address Box 506 Liberal, Kansas 67901

STATE OF Oklahoma COUNTY OF Woodward  
William R. Braley (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) William R. Braley  
Box 768 Woodward, Okla. 73801  
(Address)

SUBSCRIBED AND SWORN TO before me this 24 day of Sept. 19 74

My commission expires July 27 1977  
M. E. Blanche  
Notary Public

DRILLERS LOG

ADAMS RANCH NO. 1

|                                    |                               |   |
|------------------------------------|-------------------------------|---|
| CASING RECORD:                     | OPERATOR: Red Clark, Inc.     | DESCRIPTION:                                      |
| 8-5/8" @ 1518'<br>w/675 sax cement | CONTRACTOR: Sage Drilling Co. | C SW SE<br>Sec. 2-35S-30W<br>Meade County, Kansas |
| TOTAL DEPTH:<br>6400'              | COMMENCED: July 22, 1972      | COMPLETED: August 5, 1972                         |


| <u>FORMATION</u>    | <u>FROM</u> | <u>TO</u> | <u>REMARKS</u>           |
|---------------------|-------------|-----------|--------------------------|
| Surface Sand & Clay | 0           | 40        |                          |
| Sand & Shale        | 40          | 785       |                          |
| Sand, Shale & Gyp   | 785         | 1335      |                          |
| Shale               | 1335        | 1495      |                          |
| Anhydrite           | 1495        | 1520      |                          |
| Shale               | 1520        | 1950      |                          |
| Shale & Lime        | 1950        | 2472      |                          |
| Shale               | 2472        | 2745      |                          |
| Lime & Shale        | 2745        | 3855      |                          |
| Shale               | 3855        | 4285      |                          |
| Shale & Lime        | 4285        | 4480      |                          |
| Lime & Shale        | 4480        | 4865      |                          |
| Lime                | 4865        | 4970      |                          |
| Lime & Shale        | 4970        | 5155      |                          |
| Lime                | 5155        | 5282      |                          |
| Cherty Lime         | 5282        | 5292      |                          |
| Lime                | 5292        | 5471      |                          |
| Lime & Shale        | 5471        | 5569      |                          |
| Shale & Lime        | 5569        | 5695      |                          |
| Lime & Shale        | 5695        | 6101      |                          |
| Lime                | 6101        | 6400      | 5 1/2" @ 6388' w/175 sax |

RECEIVED  
STATE CORPORATION COMMISSION  
AUG 23 1974  
CONSERVATION DIVISION  
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

SAGE DRILLING CO., INC.

BY Clarence Michael  
Clarence Michael



Subscribed and sworn to before me this 8th day of August, 1972.

Louise K. Whitted  
Louise K. Whitted, Notary Public

My commission expires:  
November 26, 1974.