
15-175-00063-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Seward County. Sec. 16 Twp. 35S Rge. ____ (E) 31 (W)

Location as "NE/CNW¼SW¼" or footage from lines C NE/4

Lease Owner D & M Drilling Company, Inc.

Lease Name Taylor Well No. 1

Office Address 809 Union Center, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed March 18, 1962 19

Application for plugging filed ____ 19

Application for plugging approved ____ 19

Plugging commenced March 18, 1962 19

Plugging completed March 18, 1962 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production ____ 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Broadfoot, Stafford, Kansas

Producing formation ____ Depth to top ____ Bottom ____ Total Depth of Well 6445 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS — CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ____ feet to ____ feet for each plug set.

Filled hole w/heavy mud to 600'. Put Sun plug, 3 gal hulls, 30 sacks cement. Filled pipe w/heavy mud to 35'. Put 3 gal hulls, Sun plug, 10 sacks hulls.

RECEIVED
STATE CORPORATION COMMISSION
MAR 2 2 1962
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor ____

Address ____

STATE OF Kansas, COUNTY OF Sedgwick, ss.

D & M Drilling Company, Inc. (~~employee of owner~~) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) D & M Drilling Company, Inc.

Don S. Packer

Don S. Packer (Address) President

SUBSCRIBED AND SWORN TO before me this 22nd day of March, 19 62

Adela Petrik

Adela Petrik *Notary Public.*

My commission expires Nov. 5, 1962

5-49-11

15-175-00063-0000

TAYLOR #1
CNE/4 Section 16-35S-31W
Seward County, Kansas

Rigged up Rotary Tools February 23, 1962

Ran 55 jts. 8-5/8" 24# casing. 2315' overall. Set @ 2313'. Cemented bottom stage w/200 sacks common w/2% CC. Cemented top stage w/400 sacks Posmix

Filled hole w/heavy mud to 600'. Put Sun plug, 3 gal hulls, 30 sacks cement. Filled pipe w/heavy mud to 35'. Put 3 gal hulls, Sun plug, 10 sacks hulls

Tore down Rotary Tools March 18, 1962

FORMATION	FROM	TO
Sand	0	300
Redbed & Sand	300	1200
Sand & Shells	1200	1525
Shale & Anhydrite	1525	2313
Shale & Lime	2313	2540
Shale	2540	2986
Lime & Shale	2986	3826
Shale & Chalk	3826	3940
Shale	3940	4389
Shale & Lime	4389	4560
Lime	4560	5137
Lime & Chalk	5137	5260
Lime	5260	5785
Lime & Shale	5785	6243
Lime	6243	6445 RTD
		D & A

STATE OF KANSAS

COUNTY OF SEDGWICK

I, Don S. Packer, do hereby certify that the foregoing is true and correct to the best of my knowledge and belief.

Don S. Packer

Subscribed and sworn to before me this 22nd day of March, 1962.

Adela Petrik, Notary Public

My Commission Expires:
November 5, 1962

RECEIVED
STATE CORPORATION COMMISSION
MAR 28 1962
CONSERVATION DIVISION
Wichita, Kansas