


15-175-00068-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
800 Bittling Building  
Wichita, Kansas

Seward County. Sec. 15 Twp. 35S Rge. 31 (E) (W)  
Location as "NE/CNW/SW" or footage from lines. C NE/4 NW/4  
Lease Owner Aladdin Petroleum Corp.  
Lease Name Colvin Well No. 1  
Office Address 809 Petroleum Building, Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 23 19 54  
Application for plugging filed August 23 19 54  
Application for plugging approved August 23 19 54  
Plugging commenced August 25 19 54  
Plugging completed September 1 19 54  
Reason for abandonment of well or producing formation No Shows



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M.A. Rives  
Producing formation Depth to top Bottom Total Depth of Well 6158 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				13 3/8	711	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Dumped 8 sacks cement with dump bailer @ 6220  
Top of cement 6180'- Set Rock bridge @ 2685'  
Top of bridge 2670'- Dumped 15 sacks cement.  
Top of cement 2632'  
Filled with mud to 500'- Set 10' rock bridge- dumped  
20 sacks of cement. Top of cement 430'- Filled with  
mud to 30'- Set rock bridge- dumped 10 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J. & M. Casing Pulling Company  
Address Great Bend, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
(employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Leonard E. Rusch

(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of October, 19 54

Carma Haynes

Notary Public.

My commission expires April 23, 1956

24-7368-5 3-53-20M

PLUGGING  
FILE SEC 15 T 35 R 31W  
BOOK PAGE 58 LINE 13

CONSERVATION DIVISION  
WICHITA, KANSAS

To sent to Corp. Comm. w/ well plugging  
 15-175-00068 record  
 0000

DRILLERS LOG

OPERATOR: Aladdin Petroleum Corp.  
 809 Petroleum Building  
 Wichita, Kansas

ELEVATION:

WELL COMMENCED: June 20, 1954

CONTRACTOR: Midwestern Drillers  
 203 Wright Building  
 Tulsa, Oklahoma

WELL COMPLETED: July 27, 1954

TOTAL DEPTH: 6442' GL

LEASE NAME: Colvin #1

LOCATION: Cen. of S $\frac{1}{2}$  of Sec. 10 & N $\frac{1}{2}$  of Sec. 15,  
 T35S, R31W, Seward County, Kansas

CASING RECORD: Surface - Set 698' of 13 3/8" with 550 sacks of cement  
 Intermediate - Set 2685' of 9 5/8" with 600 sacks of cement  
 Production - Set 6445' of 5 1/2" with 150 sacks of cement

FORMATION	DEPTH FROM ROTARY BUSING	
	0	
Sand, clay, gravel & red bed	735	Ran 698' of 13 3/8" casing
Red bed and sand	1535	
Anhydrite and red bed	1805	
Anhydrite and shale	2430	
Anhydrite	2490	
Lime and anhydrite	2525	
Shale and anhydrite	2686	Ran 2685' of 9 5/8" casing
Shale and lime	2970	
Shale and lime	3210	
Lime and shale	3564	
Shale and lime	3855	
Shale and lime	4110	
Lime and shale	4425	
Lime and shale	4645	
Shale and lime	4770	
Lime	4815	
Shale and lime	4865	
Lime and chert	4915	
Sandy lime	4940	
Shale and lime	5096	
Lime	5140	
Lime and shale	5295	
Lime and chert	5320	
Shale and lime	5545	
Shale and lime	5840	
Shale and lime	6000	
Lime and chert	6020	
Lime and shale	6172	
Lime and shale	6202	
Shale and lime	6230	Ran Drill Stem Test
	6279	Ran Drill Stem Test
	6285	
	6365	
	6452	Ran Electric Log & D. S. T.
	6452	RB
		TD

I hereby certify that the above is a true and correct copy of Driller's Log of the Colvin #1 Well.

Subscribed and sworn to before me this 30th day of

September, 1954

F. W. Wyatt  
 Notary Public

MIDWESTERN DRILLERS

By T. F. Hansen  
 T. F. Hansen

My Commission Expires: 8-12-56

**PLUGGING**  
 FILE sec. 15 T 35 R 31W  
 BOOK PAGE 28 LINE 13