

STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Seward County, Sec. 13 Twp. 35 Rge. 31 (W)

Location as "NE/CNW 1/4 SW 1/4" or footage from lines Cen SW NE

Lease Owner J.N. Huber Corp.

Lease Name Blucher Well No. 1

Office Address Box 978 Liberal, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-18-53 19

Application for plugging filed 9-22-53 19

Application for plugging approved 9-18-53 19

Plugging commenced 9-18-53 19

Plugging completed 9-18-53 19

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well C.D. Stough

Producing formation Depth to top Bottom Total Depth of Well 6350 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|----|--------|--------|------------|
| | | | | 13 3/8 | 638' | |
| | | | | 9 5/8 | 2406' | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with mud from 6350' to 400'. Set cementing plug, 1 sack hulls, and 25 sacks cement at 400'. Filled with mud to 40'. Set cementing plug, 1 sack hulls at 40'. Filled to surface with 15 sacks cement.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor J.N. Huber Corp.

Address Box 978 Liberal, Kansas

STATE OF Kansas, COUNTY OF Seward, ss.

R.E. McDaniel (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.


(Signature) R.E. McDaniel

Box 978 Liberal, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 24 day of Sept, 1953

My commission expires July 27, 1957

23-8390-s 6-51-20M



RECEIVED
STATE CORPORATION COMMISSION

SEP 26 1953

CONSERVATION DIVISION
Wichita, Kansas

RECEIVED
STATE CORPORATION COMMISSION
WICHITA, KANSAS

BOX 343 WICHITA, KANSAS

WICHITA, KANSAS

RECEIVED

BOX 343 WICHITA, KANSAS
T.M. HIRSH, CORP.

RECEIVED

RECEIVED BY THE STATE CORPORATION COMMISSION, WICHITA, KANSAS, SEP 26 1953. THE RECEIPT IS VALID FOR THE PAYMENT OF TAXES ON THE PROCEEDS OF THE SALE OF THE PROPERTY DESCRIBED HEREIN.

SEP 26 1953

0320

C.D. STONER
ALL

DLA NOTE

- 8-18-53
- 8-18-53
- 8-18-53
- 8-25-53
- 8-18-53

DLA NOTE

BOX 343 WICHITA, KANSAS

WICHITA

T.M. HIRSH, CORP.

RECEIVED

SEP 26 1953

WELL LOG

Well Name: J.M. Huber #1 Blucher
 Location: Cen. SW NE Sec 13 Twp 35S Rge 31W
 Seward Co., Kansas
 Commenced: 8-12-53
 Completed: 9-18-53
 Test Data: Dry Hole
 Total Depth: 6350'

| <u>FORMATION</u> | <u>DEPTH</u> |
|-----------------------|--------------|
| Clay, shale & shells | 0-580' |
| Red bed and shale | 580-1650' |
| Shales and shells | 1659-1935' |
| Lime, shale & sand | 1935-2225' |
| Lime and shale | 2225-3825' |
| Lime | 3825-3845' |
| Lime and shale | 3845-4520' |
| Lime | 4520-4575' |
| Lime and shale | 4575-4790' |
| lime | 4790-5110' |
| Lime and shale | 5110-5254' |
| Hard lime | 5254-5290' |
| Lime and shale | 5290-5440' |
| Cherty lime and shale | 5440-5505' |
| Lime and shale | 5505-6350' |

STATE OF KANSAS, COUNTY OF SEWARD, SS.

I, R.E. McDaniel of the J.M. Huber Corp., being first duly sworn on oath, state: That I have knowledge of the facts, statements and matters herein contained and that the same are true and correct.

R.E. McDaniel

Subscribed and sworn to before me this 22 day of Sept 1953

J. K. Ryker
 Notary Public

My Commission Expires:

July 27, 1957

