

AUG 12 1982

STATE OF KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION
Wichita, Kansas

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Seward County, Sec. 12 Twp. 35 Rge. 31 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
200' west of C-SW-SE

Lease Owner B & B Farm Industries Inc.
Lease Name Raymond Well No. 1
Office Address Box 638, Spearman TX. 79081
Character of Well (Completed as Oil, Gas or Dry Hole)
Gas


Date Well completed 1979
Application for plugging filed 7-2-82 19
Application for plugging approved 7-8-82 19
Plugging commenced 8-4-82 19
Plugging completed 8-6-82 19
Reason for abandonment of well or producing formation
Non Commercial Value

If a producing well is abandoned, date of last production
19

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Mr. Luthi
Producing formation Council Grove Depth to top 3032' Bottom 3069' Total Depth of Well 6170'

Show depth and thickness of all water, oil and gas formations.



Locate well correctly on above
Section Plot

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface				8 5/8"	1542'	0'
Production				4 1/2"	6161'	2402'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid
was placed and the method or methods used in introducing it into the hold. If cement or other
plugs were used, state the character of same and depth placed, from _____ feet to
_____ feet for each plug set.

Plug Perf. w/3 sks. hulls & 40 sks. cement to 2740' pressured to 750 lbs.
Layed down 4 1/2" to 1600'
Pumped 35 sks. cement 1600' to 1500'
Layed down 4 1/2" to 750'
Pumped 25 sks. cement 750' to 675'
Put bridge & 10 sks. cement 40' to 0'

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Midwest Casing Pulling Service
Permit #766

STATE OF KANSAS COUNTY OF HASKELL, ss.
(Employee of owner) or (owner or operator)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of
the facts, statements, and matters herein contained and the log of the above-described well
as filed and that the same are true and correct. So help me God

(Signature) Sondra L. Eves
Box F, Sublette Ks. 67877
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of August, 1982

Sondra L. Eves
Notary Public.

My commission expires 12-6-84



RECEIVED
STATE CORPORATION COMMISSION
JUL 8 1982
CONSERVATION DIVISION
Wichita, Kansas

DRILLERS LOG

RAYMOND NO.1

CASING RECORD:	OPERATOR: B&B Farm Industries, Inc.	DESCRIPTION:
8-5/8" set @ 1542' w/750 sax cement	CONTRACTOR: Sage Drilling Co., Inc.	C SW Sec. 12-35S-31W Seward County, Kansas.
TOTAL DEPTH: 6170'	COMMENCED: December 7, 1978	COMPLETED: December 20, 1978


<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Sand & Red Bed	0	900	
Red Bed & Anhydrite	900	1550	
Shale	1550	3340	
Shale & Lime	3340	3980	
Lime & Shale	3980	6170	Logged Hole; 4 1/2" set @ 6160'; Stage Collar @ 3350'; Cemented in Two Stages w/Total of 450 sax.

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

SAGE DRILLING CO., INC.

By John R. Bartholomew
John R. Bartholomew

Subscribed and sworn to before me this 26th day of December, 1978.



Louise K. Whitted
Louise K. Whitted, Notary Public

My commission expires:
November 26, 1982.