

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 130 S. Market, Room 2078
 Wichita, KS 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

API NUMBER 15-175-217950000

LEASE NAME R.E. Adams


WELL NUMBER 1-12

3960 Ft. from S Section Line

2100 Ft. from E Section Line

SEC. 12 TWP. 35 RGE. 31 (Section W)

RECEIVED
 SEP 10 2001
 9-10-01
 KCC



TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

LEASE OPERATOR Raydon Exploration, Inc.

ADDRESS 9400 N. Broadway, Ste. 400, Oklahoma City, OK 73114 COUNTY Seward

PHONE (620) 624-0156 OPERATORS LICENSE NO. 30604 Date Well Completed 06-10-00

Character of Well D&A Plugging Commenced 8-29-01

(Oil, Gas, D&A, SMD, Input, Water Supply Well) Plugging Completed 8-30-01

The plugging proposal was approved on 8-29-01 (date)

by Steve Pfiefer (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? _____

Producing Formation Chase Depth to Top 2577 Bottom 2963 T.D. 6521

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled out |
|-----------|---------|------|----|--------------|-------------|-------------|
| | | | | <u>8 3/8</u> | <u>1875</u> | <u>-</u> |
| | | | | <u>4 1/2</u> | <u>3111</u> | <u>2245</u> |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plug were used, state the character of same and depth placed, from feet to feet each so
Mixed 1 SK hulls to 20 SK cmt. to plug perfs from 2578 to 2378. Recov. 2245 4 1/2 to pull to 1700 Circ. hole w/mud 50 SK cmt 1700 to 1550 40 SK 600 to 500 10 SK 40 to 0 Cut off & capped 8 3/8 3 ft. below G.L. Steve Middleton witness KCC

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address Route 1, Box 49BA Tyrone, OK 73951-9731 (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Raydon Exploration, Inc.

STATE OF Kansas COUNTY OF Seward, ss.

Keith Hill, agent for Raydon Exploration, Inc. (Employee of Operator) or (Operator) above-described well, being first duly sworn on oath, says: That I have knowledge of the fact statements, and matters herein contained and the log of the above-described well as filed to the same are true and correct, so help me God.

(Signature) _____

(Address) Crown Consulting, Inc.

SUBSCRIBED AND SWORN TO before me this 6th day of September, 2001

[Signature]

Notary Public

My Commission Expires:

