

15-175-00026-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Seward County, Sec. 11 Twp. 35 Rge. (E) 31 (W)

NORTH



Locate well correctly on above
Section Plat

Location as "NE/CNW/SW" or footage from lines
Lease Owner Tennessee Gas Transmission Company
Lease Name E. J. McCreight Well No. 1
Office Address P. O. Box 163 - Great Bend, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 19
Application for plugging filed April 21 19 59
Application for plugging approved 19
Plugging commenced April 20 19 59
Plugging completed April 21 19 59
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production None 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Merle A. Rives
Producing formation ----- Depth to top --- Bottom --- Total Depth of Well 6260 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	2460	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Bottom plug set @ 550' w/35 sx cmt.
Top plug set @ 35' w/15 sx cmt.
Hole was mudded from TD to bottom of bottom plug
and from top of bottom plug to bottom of top plug.

STATE OF KANSAS
MAY 1 1959
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor: Capitt Drilling, Inc.
Address: 814 Union Center, Wichita, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.
Glen E. Armour (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Glen E. Armour
P. O. Box 163 - Great Bend, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 30 day of April, 1959

My commission expires October 13, 1962
John Larson Notary Public.

PLUGGING
FILE SEC. 11 T. 35 R. 31 W
BOOK PAGE 33 LINE 8

ROTARY DRILLING LOG

OPERATOR: Tennessee Gas Transmission Company
E. J. McCreight #1
C NE SW Sec. 11-35S-31W,
Seward County, Kansas

CONTRACTOR: Capitt Drilling, Inc.
COMM: 3/14/59
COMP: 4/21/59

Formations:

Soil & Clay	40'
Shale & Sand	235'
Sand & Shale	790'
Shale & Shells	935'
Shale - Strk. lime	1165'
Red Bed	1285'
Shale & Lime	1435'
Shale	1470'
Shale & Lime	1510'
Shale & Shells	1679'
Shale & Lime	2055'
Lime w/shale	2115'
Lime & Shale	2205'
Shale & Lime	2265'
Shale w/lime	2355'
Lime & Shale	2435'
Lime	2460'
Shale, Lime & Anhydrite	2535'
Anhydrite, Lime w/sand	2670'
Lime & Shale	2746'
Lime w/streaks chert	2800'
Lime	2817'
Sand & Lime	2850'
Lime & Shale	2932'
Chalky Lime	2970'
Lime w/Chalk	2994'
Lime w/chert	3008'
Lime w/shale	3033'
Lime	3132'
Lime & Shale	3195'
Lime w/chalk	3210'
Lime & chalky lime	3284'
Lime w/chalk	3460'
Chalky Lime	3560'
Lime w/chalk	3655'
Lime w/shale streaks	3730'
Chalky Lime	3810'
Lime	3848'
Lime w/strks chalk & shale	3947'
Shale	4174'
Shale w/strks. lime	4424'
Shale	4470'
Lime	4590'
Lime & Shale	4640'
Lime	4719'
Lime w/Sandy lime	4753'
Lime	4888'
Chalky Lime	4930'
Lime	4954'
Shale	4966'
Lime	4990'
Lime w/Chert	5022'

Remarks: Set 8-5/8" surface casing at 2459' cemented with 110 sacks cement on bottom, cemented through DV tool set at 602' w/500 sx. Poz-mix.

FORMATIONS: (Cont.)

Lime	5276'
Lime & Shale	5305'
Lime	5650'
Lime w/Shale Streaks	5702'
Lime & Shale	5744'
Shale w/Strks. Lime	5805'
Lime w/Shale Streaks	5830'
Lime & Shale	5954'
Lime	5986'
Lime Shale & Sand	6003'
Core #1	6005'
Core #2	6011 $\frac{1}{2}$ '
Shale	6028'
Lime	6071'
Lime & Shale	6097'
Core #3	6118'
Shale & Lime	6162'
Lime	6260'
Rotary Total Depth (D&A)	6260'

RECEIVED
STATE CORPORATION COMMISSION

MAY 1 1959

CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

CAPITT DRILLING, INC.

R. R. McNicol

R. R. McNicol

PLUGGING
FILE SEC. 11 T. 35. R. 31 W.
BOOK PAGE 33 LINE 8