


15-175-20489-0000

WELL PLUGGING RECORD

Give All Information Completely  
 Make Required Affidavit

COUNTY Seward SEC. 8 TWP. 35S RGE. 31 E/W  
 Location as in quarters or footage from lines:



Locate Well  
 correctly on above  
 Section Platt.

Lease Owner DIETRICH EXPLORATION COMPANY, INC.  
 Lease Name Texaco Fee (formerly Baty) Well No. #8-31  
 Office Address 410 Seventeenth Street, #2450  
Denver, Colorado 80202  
 Character of Well (Completed as Oil, Gas or Dry Hole): Dry Hole  
 Date Well Completed October 28, 1980  
 Application for plugging filed March 15, 1982; verbal approval  
 Plugging commenced October 28, 1980 granted/ 10/27/80  
 Plugging completed October 28, 1980  
 Reason for abandonment of well or producing formation Testing  
of potential zones indicated lack of commercial production  
 Was permission obtained from the Conservation Division or it's  
 Agent's before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas  
 Producing formation None Depth to top NA bottom NA T.D. 6,350'  
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
No oil or gas zones		0'	60'	20"	60'	-0-
Water zones 280-300' and other surface sand intervals		0'	1520'	8-5/8"	1,520'	-0-

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

- Set 60 sx plug @ 1,550'
- Set 25 sx plug @ 700'
- Set 10 sx plug from 40' to 0'
- Set 5 sx in rat hole
- Set 5 sx in mouse hole
- 105 sx total; class "H" cement with 2% Gel
- Left hole conditioned with heavy drilling mud.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Halliburton Services (Liberal, Kansas District), Duncan, Oklahoma

CITY AND  
 STATE OF COLORADO COUNTY OF DENVER, ss.

RAY F. DIETRICH (employee of owner) ~~is a duly sworn and qualified~~ of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the ~~same~~ are true and correct. So help me God.

(Signature) Ray F. Dietrich  
Denver, Colorado 80202  
 (Address)

RECEIVED  
 MAR 17 1982  
 CONSERVATION DIVISION  
 WICHITA, KANSAS

SUBSCRIBED AND SWORN TO before me this 15th day of March, 19 82

Heumonde  
 Notary Public.

My Commission expires: Nov. 27, 1983  
 whose address is 410 Seventeenth Street, #2450  
Denver, Colorado 80202

DRILLER'S LOG

DIETRICH EXPLORATION COMPANY, INC.

Surface Casing:

TEXACO FEE #1  
C-NW/4 NE/4 Sec. 8-35S-31W  
Seward County, Kansas

Drilled 1520' of 12 1/4" hole. Ran 36 jts.  
8-5/8" 24# new Surface Casing, 1522' OA,  
set @1520'. Lost circulation @1218', 20  
bbls. Cemented w/600 sks Light, 2%CC, 1/4#  
flocele; 200 sks Class H, 3%CC. Cement  
did circ. Plug down @ 7:00AM 10/4/80.

Commenced: October 3, 1980  
Completed: October 28, 1980

Total Depth:  
6350'

FORMATION	FROM	TO	REMARKS
Sand	0'	1490'	
Sand, Anhydrite	1490'	1550'	
Sand	1550'	1895'	
Shale	1895'	2502'	
Shale, Lime	2502'	3000'	
Lime, Shale	3000'	3485'	
Lime	3485'	3720'	
Shale, Lime	3720'	4245'	
Lime, Shale	4245'	4725'	
Shale	4725'	5255'	
Lime, Shale	5255'	5800'	
Lime	5800'	5910'	
Lime, Shale	5910'	6195'	
Lime	6195'	6245'	Logged well
Lime, Shale	6245'	6350'	LTD 6346'
RTD		6350'	P&A

I certify that this is a true and correct copy of the log on the above captioned well to the best of my knowledge.

NRG Drilling, Inc.

By R.J. Patrick  
R.J. Patrick, President

Subscribed and sworn to before me this 30th day of October 19 80

V. Kay Lucas  
Notary Public

My commission expires:

