

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-175-20,638-0000

LEASE NAME LOFLAND "A"

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 1

1320 Ft. from S Section Line

1320 Ft. from E Section Line

SEC. 6 TWP. 35S RGE. 31 (E or W)

COUNTY Seward

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 9/20/82

Character of Well Gas

Plugging Commenced 2/14/87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 2/18/87

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? District I

Is ACO-1 filed? yes If not, is well log attached? _____

Producing Formation Morrow Depth to Top 5942 Bottom 5956 T.D. 6590

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
Morrow	Gas	Surf	1653	8 5/8	1653	-0-
Marmaton	Water	Surf	6110	4 1/2	6110	3030

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Pumped 1 sx hulls and 25 sx cmt. Displace to 5200' w/rubber plug. Shot off 4-1/2" casing at 3030'. Pumped 30 sx cmt 2900-3100'. Pumped 50 sx cmt 1700' to 1600'. Pumped 30 sx cmt 600'-550'. Pumped 10 sx cmt from 30' to surface. Cut off 8-5/8" csg 3' below ground and cap.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Production Manager (Employee of Operator) or ~~(Operator)~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) Box 351, Liberal, Kansas 67901

SUBSCRIBED AND SWORN TO before me this 5th day of May, 1987

Glenna S. Salley

My Commission Expires:

Notary Public
-GLENN S. SALLEY
NOTARY PUBLIC
STATE OF KANSAS
MY APPT. EXPIRES 1-6-91

Notary Public
STATE CORPORATION COMMISSION

MAY 6 1987

Form CP-4
Revised 08-84

JOHNSON Drilling Company, Inc.



OFFICES IN
EVANSVILLE, INDIANA
TEL (812) 424-8291
OKLAHOMA CITY, OKLAHOMA
TEL (405) 943-7667
LIBERAL, KANSAS
TEL (316) 624-7731

REPLY TO:

3535 N. W. 58th - Suite 710
Oklahoma City, Oklahoma 73112

August 23, 1982

ANADARKO PRODUCTION COMPANY
P. O. BOX 351
LIBERAL, KANSAS 67901

ATTN: PAUL GATLIN

DRILLERS LOG for:	LOFLAND "A" # 1
0' - 300'	Surface, Clay, & Sand
300' - 820'	Sand & Redbed
820' - 1647'	Redbed, Shale, & Sand
1647' - 1657'	Anhydrite
1657' - 2675'	Shale
2675' - 3253'	Lime & Shale
3253' - 3505'	Shale
3505' - 6590'	Lime & Shale

JOHNSON DRILLING COMPANY, INC.

Signed by: Claude D. Moore
Claude D. Moore, Manager

STATE OF OKLAHOMA:

STATE CORPORATION COMMISSION

COUNTY OF OKLAHOMA:

JAN 28 1982

CONSERVATION DIVISION
Wichita Kansas

Subscribed and sworn to before me this 23rd day of August, 1982.

Barbara Kelly Notary Public

My Commission Expires:

October 24, 1984