

15-129-20213-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER _____

LEASE NAME INTERSTATE UNIT

WELL NUMBER 79

1320 Ft. from S Section Line

50 Ft. from W Section Line

SEC. 21 TWP. 34 RGE 43 (E) or (W)

COUNTY MORTON

Date Well Completed _____

Plugging Commenced 12-15-98

Plugging Completed 1-12-99

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well WATER SUPPLY WELL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 12-5-98 (date)

by GARY WINTERS (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation MORROW Depth to Top 4111 Bottom 4140 T.D. 4210

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|-----------|---------|------|------|-------|--------|------------|
| MORROW | WATER | 4111 | 4140 | 8-5/8 | 1142 | 0 |
| | | | | 5-1/2 | 4205 | 983 |
| | | | | 2-7/8 | 3581 | 1000 |
| | | | | | | |

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet each set. PMP 10.5 RW, 21 SXS CMT @ 3500. DISPLACE W/ 9 RW. PMP 50 SXS @ 2222. DISPLACE W/ 8 RW. CUT 2-7/8" @ 1000. LD HOLE W/ MUD. SHOOT OFF 5-1/2" @ 983. PMP 30 SXS FROM 1000 TO 900. PULL TO 550. PMP 40 SXS @ 550 TO 450. PULL TO 40. PMP 10 SXS @ 40 TO 0. CUT OFF AND CAP 4' BELOW GL. STATE WITNESS GARY WINTERS

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515 1-25-99

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Shawn D. Young

SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 21st day of January, 1998.

Shirley J. Childers
Notary Public

My Commission Expires: _____

