


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202

Morton County, Sec. 21 Twp. 34S Rge. 43 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines
C SW NW

Lease Owner Unitized - Anadarko Production Company
Lease Name INTERSTATE UNIT Well No. 37
Office Address P. O. Box 351, Liberal, Kansas 67901
Character of Well (Completed as Oil, Gas or Dry Hole) Oil



Locate well correctly on above
Section Plot

Date Well completed June 27 1956
Application for plugging filed March 3 1981
Application for plugging approved March 17 1981
Plugging commenced May 14 1981
Plugging completed May 16 1981

Reason for abandonment of well or producing formation
Condition of casing was very poor
If a producing well is abandoned, date of last production
May 1976

Was permission obtained from the Conservation Division or
its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas

Producing formation Purdy Morrow Depth to top 4121 Bottom 4176 Total Depth of Well 4270

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				7"	1140	None
				4-1/2"	4248	1990'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Spotted 20 sxs common cmt 2020-1971; 50 sxs common cmt 1100-840'; 25 sxs common cmt 600-470'; 10 sxs common cmt 40-0'.

RECEIVED
STATE CORPORATION COMMISSION
5-2-81
MAY 28 1981

(If additional description is necessary, use back of this sheet)

Name of Plugging Contractor Sargent's Casing Pulling Service
Wichita, Kansas

STATE OF KANSAS COUNTY OF SEWARD, ss.
Paul Campbell (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul Campbell
P. O. Box 351, Liberal, Kansas 67901
(Address)

SUBSCRIBED AND SWORN TO before me this 27th day of May, 1981

STATE NOTARY PUBLIC
BEVERLY J. WILLIAMS
Seward County, Kansas
My Appt. Exp. 11/21/82

Beverly J. Williams
Notary Public.

My commission expires November 21, 1982

15-129-10497-0000

DRILLER'S LOG

Well Name Interstate 04

Company Panhandle Eastern Pipe Line Company

Well Location Section 21-34S-43W

Contractor Nye & Snell Drilling Company

Center of SW of NW

Elevation 3470.35

County Morton State Kansas

Drilling Commenced June 11, 1956

State Test 401 BOPD

Drilling Completed June 27, 1956

Method of Production Pumping

Well Completed July 4, 1956

Source of Data State Potential

Well Connected

ROTARY LOG

<u>Description of Formation</u>	<u>Top</u>	<u>Bottom</u>
Sand and red bed	0	104
Red bed	104	158
Red bed and lime	158	715
Red bed, shale and lime	715	1125
Anhydrite	1125	1160
Red bed, shale and sand	1160	1520
Shale and sand	1520	1896
Shale and shells	1896	2075
Shale, shells and sand	2075	2235
Sand and shale	2235	2345
Shale	2345	2453
Shale	2453	2525
Lime and shale	2525	2612
Lime and shale	2612	2735
Shale and lime	2735	2800
Lime and shale	2800	2895
Lime and shale	2895	2969
Lime and shale	2969	3070
Lime and shale	3070	3175
Lime and shale	3175	3282
Lime and shale	3282	3395
Sand, lime and shale	3395	3460
Lime and shale	3460	3582
Lime, shale and sand	3582	3681
Lime, shale and sand	3681	3775
Lime and shale	3775	3838
Lime and shale	3838	3904
Lime and shale	3904	3945
Lime and shale	3945	3980
Lime and shale	3980	4045
Lime and shale	4045	4110
Lime and shale	4110	4130
Sand and shale	4130	4230
Shale and sand	4230	4270 T. D.

RECEIVED COMMISSION

MAR 16 1981

CONSERVATION DIVISION
Wichita, Kansas

REVISION NO. 1
DATE
BY

EXPLORATION SHEET
DRILLER'S LOG

Well Name Interstate 04

Page 2 (Con't)

Well Location C of SW NW Sec 21-34S-43W

FORMATION TOPS

Wabaunsee	2458
Topeka	2654
C. S. O. Lansing	2891
Lansing	3092
Cherokee	3821
Morrow	4078
Purdy Sand	4121

PERFORATIONS

4140 - 4160

WELL TREATMENT RECORD

Well not treated.

CASING RECORD

- Set 104' of 10-3/4" conductor pipe w/125 sx cmt.
- Set 1140' of 7" casing w/500 sx cmt.
- Set 4248' of 4 1/2" casing w/300 sx cmt.
- Set 4154' of 2" tubing.

RECEIVED BY MISSION

MAR 16 1981

CONSERVATION DIVISION
Wichita, Kansas