

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-10500 0000
API NUMBER NA (SPUD 1956)

LEASE NAME INTERSTATE UNIT

WELL NUMBER 49

660 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 21 TWP. 34 RGE 43 (E) or (1)

COUNTY MORTON

Date Well Completed 12-14-1956

Plugging Commenced 1-13-2000

Plugging Completed 1-18-2000

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well INJECTION

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 1-4-2000 (date)

by GARY WINTERS (KCC District Agent=s Name)

Is AC0-1 filed? YES If not, is well log attached?

Producing Formation INTERSTATE PURDY Depth to Top 4107 Bottom 4154 T.D. 4260

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
MORROW	OIL	4107	4514	7"	1123	0
				4 1/2"	4240	1158

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
LOAD HOLE W/ MUD. PMP 1 SK HULLS AND 20 SXS CMT @ 4107-3907. PULL FREE POINT AND SHOOT OFF 4 1/2" CSG @ 1158. PMP 50 SXS CMT @ 1150-1000. PMP 25 SXS CMT @ 550 - 450. PMP 10 SXS CMT @ 40-3. CUT OFF AND CAP 7" CSG 3' BELOW GL.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, SS.


SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 1/31st day of January 2000

My Commission Expires



Form CP-4
Revised 05-88

RECEIVED
STATE CORPORATION COMMISSION

FEB - 3 2000

CONSERVATION DIVISION
Wichita, Kansas