

RECEIVED
NOV 16 2001
KCC WICHITA

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well INJECTION EDR

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-15-01 (date)

by GARY WINTERS (KCC District Agent's Name).

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation PURDY MORROW Depth to Top 4134 Bottom 4174 T.D. 4250

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
PURDY MORROW	OIL	4134	4147	8 5/8	1161	0
				4 1/2	4230	1257

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. CIRC WITH 9PPG MUD. PUMP 2 SXS HULLS AND 25 SXS CMT FROM 4134-3934. SHOOT OFF CSG @ 1257. PUMP 50 SXS CMT FROM 1200-1050. PUMP 40 SXS CMT FROM 600 TO 480. PUMP 10 SXS CMT FROM 40 TO SURFACE. CUT OFF 8 5/8 CSG 3' BELOW AND CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151

Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

CRAIG R. WALTERS, P.E., DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Signature) Craig R. Walters
CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER



Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 12 day of October, 2001

Lori Pearson
Notary Public

My Commission Expires: 2/26/05

OR