

15-129-10505-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 11-3-56

LEASE NAME INTERSTATE UNIT

WELL NUMBER 31

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 21 TWP. 34S RGE. 43 ~~REX~~OR(W)

COUNTY Morton

Date Well Completed 11-3-56

Plugging Commenced 2-12-91

Plugging Completed 2-14-91

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P.O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 2-6-91 (date)

by Dick Kapp (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? _____

Producing Formation Morrow Depth to Top 4153 Bottom 4188 T.D. 4246

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				7"	1115	0
				4 1/2"	4241	1202

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. TIH w/1 1/4" tbg to 2000'. Ran 1 1/4" to 4133'. Circ hole w/9.0 ppg mud. Spot 10 sxs cmt @ 4133-4033'. Lay dwn 1 1/4" tbg. Pull freepoint @ 1300'. Shot off 4 1/2" csg @ 1202'. Spot 50 sxs cmt from 1202-1102'. Pull 4 1/2" csg to 650' and spot 25 sxs cmt from 650-550'. Pull 4 1/2" csg to 50' and spot 10 sxs cmt from 50-3'. Cut off and cap 7" csg 3' below GL. Clean location
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams - Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams
Beverly J. Williams - Engineering Tech.
(Address) P.O. Box 351, Liberal, KS 67905-0351

RECEIVED
STATE CORPORATION COMMISSION

APR 03 1991 SUBSCRIBED AND SWORN TO before me this 2nd day of April, 19 91

Cheryl Steers
Notary Public

CONSERVATION DIV. (A)
Wichita, Kansas My Commission Expires:

