

WELL PLUGGING RECORD

Give All Information Completely
 Make Required Affidavit

COUNTY Morton SEC. 21 TWP. 34S RGE. 43 X/E/W
 Location as in quarters or footage from lines:
1980' FWL & 1980' FNL

		21	

Lease Owner Anadarko Production Company
 Lease Name Interstate Unit Well No. 38
 Office Address P. O. Box 351, Liberal, KS 67901
 Character of Well (Completed as Oil, Gas or Dry Hole): Oil
 Date Well Completed 10/26/56
 Application for plugging filed 7/25/83
 Plugging commenced 8/24/83
 Plugging completed 8/24/83
 Reason for abandonment of well or producing formation An attempt to convert ISU #38 to an injection well resulted in loss of the wellbore.
 Was permission obtained from the Conservation Division or it's Agent's before plugging was commenced? yes

Locate Well correctly on above Section Platt.

Name of Conservation Agent who supervised plugging of this well Bob Tarbutton
 Producing formation Purdy Morrow Depth to top 4142 bottom 4176 T.D. 4240
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

Casing Record

Formation	Content	From	To	Size	Put in	Pulled Out
Purdy Morrow	Oil	4111	4176	7"	1141'	None
				4-1/2"	4225'	None
				2-3/8"	4122'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

The unsuccessful attempt to convert Interstate Unit No. 38 to a tertiary injection well resulted in a string of 2-3/8" fiberglass tubing being cemented inside the 4-1/2" production casing. The 2-3/8" tubing is cemented on the outside from 4125' to the surface, and the inside of the 2-3/8" tubing contains cement from 4125' to 3151'. The well was plugged and abandoned by placing a cement plug from 300' to 3' in the tubing. The surface casing, production casing, and tubing were cut off approximately 3' below the surface and capped.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor None

STATE OF KANSAS COUNTY OF SEWARD, ss.
Paul Campbell (employee of owner) or (~~xxxxxxx~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul Campbell
P. O. Box 351, Liberal, KS 67901
 (Address)

SUBSCRIBED AND SWORN TO before me this 22nd day of Sept, 1983

Beverly J. Williams
 Notary Public.

My Commission expires:

BEVERLY J. WILLIAMS
 Seward County, Kansas
 My Comm. Expires: November 21, 1986

RECEIVED
 STATE CORPORATION COMMISSION

SEP 27 1983

CONSERVATION DIVISION
 Wichita, Kansas

15-129-10504-0000
file

DRILLERS LOG

Well Name Interstate # 07 (TSU#38) Company Panhandle Eastern Pipeline Co.
 Well Location C of SE NW of Section Contractor Nye & Snell Drilling Co.
21, Twp 34, Rng 43 Elevation 3471.58
 County Morton State Kansas Drilling Commenced Oct. 2, 1956
 State Test Flowed 1946 37 BOPD Drilling Completed Oct. 15, 1956
 Method of Production Flowing Well Completed Oct. 26, 1956
 Source of Data State Potential Well Connected

ROTARY LOG

<u>Description of Formation</u>	<u>Top</u>	<u>Bottom</u>
Red bed and gravel	0	118
Red bed	118	474
Red bed and shale	474	779
Red bed, shale and anhy	779	1145
Shale	1145	1254
Shale and shells	1254	2025
Shale	2025	2235
Lime and Shale	2235	3960
Lime	3960	3990
Lime and Shale	3990	4113
Sand	4113	4120
Shale and Lime	4120	4140
Sand, shale, lime	4140	4240

FORMATION TOPS

Wabaunsee	2463
Topeka	2662
CSO Lansing	2899
Lansing	3104
Cherokee	3833
Morrow Top	4092
Upper Morrow Sand	4110
Prudy	4136

PERFORATIONS

4142 - 4162
4111 - 4118

WELL TREATMENT RECORD

Well not treated

Casing Record

Ran 113' of 10 3/4" cond pipe w/100 sx common cmt.
 7 Ran 1141' of surf csg w/750 sx pozmix cmt
 Ran 4225' of 4 1/2" prod csg. w/300 sx pozmix cmt.

RECEIVED
STATE CORPORATION COMMISSION

III 27 1983

WICHITA, KANSAS