

15-129-20525-0000

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
Finney State Office Building  
30 South Market, Rm 2078  
Wichita, Kansas 67202

WELL PLUGGING RECORD  
K.A.R.-82-3-117

API NUMBER ~~15-129-20525-0000~~  
LEASE NAME INTERSTATE UNIT  
WELL NUMBER 37A

TYPE OR PRINT  
NOTICE: Fill out completely  
and return to Cons. Div.  
office within 30 days

3300 Ft. from S Section Line  
4595 Ft. from E Section Line

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION  
ADDRESS P.O. BOX 351, LIBERAL, KS 67901-0351  
PHONE # ( 316 ) 624-6253 OPERATORS LICENSE NO. 4549

SEC. 21 TWP. 34S RGE. 43 ( E ) or ( )  
COUNTY MORTON

Character of Well WATERFLOOD INJECTOR  
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Date Well Completed 5/18/81  
Plugging Commenced 8/30/99  
Plugging Completed 9/3/99

The plugging proposal was approved on 8/24/99 (date)  
by GARY WINTERS (KCC District Agent=s Name)

Is ACO-1 filed? YES If not, is well log attached? \_\_\_\_\_

Producing Formation INTERSTATE PURDY Depth to Top 3920 Bottom 4210 T.D. 4260

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
PRUDY	OIL	3920	4210	4-1/4	4260	2641
				8-5/8	1106	0

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_ feet to \_\_\_ feet each set. PLUG PERES 4120-3920 W/ 1 SK HULLS & 20 SXS CMT. TAG @ 3887. SHOOT 4-1/2" CSG @ 2910 & 2641. CAME LOOSE @ 2641. TOH W/ CSG. SPOT 50 SXS CMT @ 1200-1050. SPOT 15 SXS @ 50 - 3'. CUT OFF AND CAP 8-5/8" CSG 3' BELOW GL. RDMQ, RESTORE LOCATION.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT & HORTON PLUGGING, INC. License No. 31151

Address RT. 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.  
SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) Shawn D. Young  
SHAWN D. YOUNG, DIVISION PRODUCTION ENGINEER

(Address) P.O. BOX 351, LIBERAL, KS 67901-0351

SUBSCRIBED AND SWORN TO before me this 7th day of October, 1998

Shirley Childers  
Notary Public

My Commission Expires:



Form CP-4  
Revised 05-88

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 12 1999  
CONSERVATION DIVISION  
Wichita, Kansas