

STATE OF KANSAS
STATE CORPORATION COMMISSION
Finney State Office Building
30 South Market, Rm 2078
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-20564 - 00-00

LEASE NAME INTERSTATE UNIT

WELL NUMBER 94

85 Ft. from S Section Line

4080 Ft. from E Section Line

SEC. 21 TWP. 34 RGE 43 (E) or (W)

COUNTY MORTON

Date Well Completed 03-24-83

Plugging Commenced 10-21-01

Plugging Completed 10-26-01

LEASE OPERATOR ANADARKO PETROLEUM CORPORATION

ADDRESS 701 S TAYLOR, STE 400 AMARILLO, TX 79101

PHONE # (806) 457-4600 OPERATORS LICENSE NO. 4549

Character of Well OIL

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-17-01 (date)

by GARY WINTERS (KCC District Agent's Name)

Is AC0-1 filed? YES If not, is well log attached? _____

Producing Formation PURDY Depth to Top 4119 Bottom 4135 T.D. 4245

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put In | Pulled Out |
|--------------|---------|------|------|-------|--------|------------|
| PURDY MORROW | OIL | 4119 | 4135 | 8 5/8 | 1169 | 0 |
| | | | | 5 1/2 | 4244 | 2200 |
| | | | | | | |
| | | | | | | |

Describe in detail, the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from ___ feet to ___ feet each set. CIRC WITH 9PPG MUD. PUMP 10 SXS CMT ON CIBP FROM 4070-3990. SHOOT OFF 5 1/2" CSG AT 2200'. PUMP 50 SXS CMT AT 1200-1050. PUMP 40 SXS CMT AT 600-480. PUMP 10 SXS CMT 40-SURFACE. CUT OFF 8 5/8" CSG 3' BELOW GI AND CAP.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor SARGENT AND HORTON PLUGGING, INC. License No. 31151


Address RT 1 BOX 49BA, TYRONE, OK 73951-9731 PHONE: (580) 854-6515

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: ANADARKO PETROLEUM CORPORATION

STATE OF KANSAS COUNTY OF SEWARD, ss.

CRAIG R. WALTERS, DIVISION PRODUCTION ENGINEER (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

Craig R. Walters
(Signature) CRAIG R. WALTERS, P.E., DIV. PROD. ENGINEER



Address) 701 S. TAYLOR, STE 400 AMARILLO, TX 79101

SUBSCRIBED AND SWORN TO before me this 12 day of October, 20 01

Lori Pearson
Notary Public

My Commission Expires: 2/26/05

GR