

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-29-10405-0004

API NUMBER 9-13-55 drill date

LEASE NAME Interstate Unit*

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 47

660 Ft. from S Section Line

1980 Ft. from E Section Line

SEC. 20 TWP. 34S RGE. 43 KKKor(W)

COUNTY Morton

Date Well Completed 10-18-55

Plugging Commenced 6-30-92

Plugging Completed 7-3-92

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Input

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 6-29-92 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? -

Producing Formation Morrow Depth to Top 4154 Bottom 4169 T.D. 4270

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	1153	0
				5 1/2	4220	1222'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Release pkr. Ld 200' 2 3/8 tbg, circ hole w/mud. Pmp 1' sk hulls & 20 sxs cmt @ 4154-3954.
Ld 2000' 2 3/8 tbg, TOH w/129 jts tbg. Shot off 5 1/2 csg @ 1222. Pull csg to 1190 & spot 40
sxs cmt @ 1190-1090. Pull csg to 650 & spot 35 sxs cmt @ 650-550. Ld hole w/mud. Spot 40 sxs
cmt @ 40-3'. Cut off 8 5/8 csg 3' below ground level & cap well. Rec 38 jts 5 1/2 csg (1222').
(If additional description is necessary, use BACK of this form.) Restore location.

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547 KCC witnessed.

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of
above-described well, being first duly sworn on oath, says: That I have knowledge of the facts,
statements, and matters herein contained and the log of the above-described well as filed that
the same are true and correct, so help me God.

(Signature) Beverly J. Williams


(Address) P.O. Box 351, Liberal, KS 67905-0351

*Formerly JM Huber Block "A" No. 2

SUBSCRIBED AND SWORN TO before me this 4th day of August, 1992

CONSERVATION DIVISION
WICHITA, KS

My Commission Expires:



CHERYL STEERS Notary Public