

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-120-20,609-0000

LEASE NAME INTERSTATE "F"

WELL NUMBER 6

SPOT LOCATION 760' FEL & 1320' FNL

SEC. 20 TWP. 34 SRGE. 43 (X) or (W)

COUNTY Morton

Date Well Completed 4/7/82

Plugging Commenced 1/26/84

Plugging Completed 1/28/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Production Company

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE # (316) 624-6253 OPERATORS LICENSE NO. 5469

Character of Well D&A
(Oil, Gas, D&A, SHD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? yes

Which KCC/KDHE Joint Office did you notify? Dodge City, Kansas

Is ACO-1 filed? yes If not, Is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 5400

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	1168'	-0-
				4-1/2"	3462'	1034'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from feet to feet each set.

Shot off csg 1242', could not pull, shot off csg 1034', pull to 1000', spot 40 sx cmt 1000-900', pull csg to 700', spot 40 sx cmt 700-600', pulled total 25 jts, 1034' 4-1/2" 10.5# csg, spot 10 sx cmt 40-3', cap well.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547
Address 620 S. Lincoln, Liberal, Kansas 67901

STATE OF KANSAS COUNTY OF SEWARD, ss.

Paul Campbell

(employee of operator) or

~~operator~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well and that the same are true and correct, so help me God.

RECEIVED
STATE CORPORATION COMMISSION

(Signature) Paul Campbell


(Address) Box 351, Liberal, KS 67901

APR 02 1984

RECEIVED AND SWORN TO before me this 30th day of March, 1984
Wichita, Kansas

Beverly J. Williams
Notary Public

My Commission expires November 21, 1986



GABBERT-JONES, INC.
 WICHITA, KANSAS
 DRILLERS' WELL LOG

Interstate "F" #6
 660' FEL & 1320' FNL
 Sec 20-34S-43W
 Morton County Kansas

Commenced: 3-4-82

Completed: 3-21-82

OPERATOR: ANADARKO PRODUCTION CO.

From	Depth To	Formation	Remarks
0	525	Sand-Redbed	
525	868	Sand-Redbed-Anhy	
868	1170	Redbed-Sand	
1170	1301	Anhy-Lime-Shale	
1301	5400	Lime-Shale	
	5400 - TD		

Ran 28 jts of 24# 8 5/8" csg
 set @ 1169' Cemented w/
 500 sks Posmix 4% Gel
 2% CC + 200 sks Common
 2% CC PD @ 1:45 a.m.
 3-6-82

Ran 85 jts of 10 1/2# 4 1/2" csg
 set @ 3461' Cemented w/
 350 sks L. W. + .5% CFR-2
 + 250 sks Salt Sat Posmix
 .5% CFR-2
 PD @ 6:30 a.m. 3-21-82

STATE OF KANSAS)
) SS
 COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above
 Drillers' Well Log is true and correct to the best of my knowledge and belief
 and according to the records of this office.

GABBERT-JONES, INC.

James S. Sutton II
 JAMES S. SUTTON II

Suscribed and sworn to before me this 29th day of March, 1982.

Elizabeth J. Edwards
 ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

RECEIVED
 STATE CORPORATION COMMISSION
 SEP 16 1983
 CONSERVATION DIVISION
 Wichita, Kansas

