

STATE OF KANSAS
STATE CORPORATION COMMISSION
209 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-10401-0000

API NUMBER 3-9-56

LEASE NAME Interstate Unit

WELL NUMBER 27

4620 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 20 TWP. 34SRGE. 43 (N) or (W)

COUNTY Morton

Date Well Completed 3-9-56

Plugging Commenced 11-6-89

Plugging Completed 11-10-89

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 10-27-89 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? NA If not, Is well log attached? Physical Productivity Report filed

Producing Formation Purdy Morrow Depth to Top 4192 Bottom 4212 T.D. 4265

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Oil	4192	4212	8 5/8"	1119	0
				5 1/2"	4265	2015

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Circ hole w/9 PPG drilling mud. Spot 20 sxs cmt @ 4090-3890. TOH w/2 3/8 tbg. Shoot off 5 1/2 csg @ 2015. Spot 25 sxs cmt @ 2015-1915. Spot 50 sxs @ 1219-1019. 35 sxs cmt 650-480 and 10 sxs cmt 33-3. Cut off 8 5/8 csg and cap 3' below ground level. Weld on steel plate. Cmt type common. Restore location.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547-7777

Address 620 South Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation JAN 9 1990

STATE OF Kansas COUNTY OF Morton, ss. 1-9-90

M. L. Pease, Division Production Manager (Employee of Operator) or (Operator) of

above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

(Address) M. L. Pease
Box 351, Liberal, KS 67905-0351

SUBSCRIBED AND SWORN TO before me this 5th day of January, 19 90

Cheeryl Steers
Notary Public

My Commission Expires:

