

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-129-20343 - 0000

LEASE NAME Interstate Unit

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 85

990 Ft. from S Section Line

1650 Ft. from E Section Line

LEASE OPERATOR Anadarko Petroleum Corporation

SEC. 20 TWP. 34S RGE. 43 (W)

ADDRESS P. O. Box 351, Liberal, Kansas

COUNTY Morton

PHONE# (316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 12-9-77

Character of Well Oil

Plugging Commenced 4-1-93

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 4-4-93

The plugging proposal was approved on 3-31-93 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, Is well log attached? -

Producing Formation Interstate Purdy Depth to Top 4192 Bottom 4200

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation | Content | From | To | Size | Put in | Pulled |
|-----------|---------|------|----|-------|--------|--------|
| | | | | 8 5/8 | 951 | 0 |
| | | | | 4 1/2 | 4221 | 830 |
| | | | | | | |
| | | | | | | |

RECEIVED
APR 28 1993
KANSAS CORPORATION COMMISSION
CONSERVATION DIVISION
WICHITA, KS

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. MIRU. TIH w/1000' 1 1/4 workstring to 4192. Circ hole w/mud. Pmp 1 sk hulls & 20 sxs cmt from 4192-3992'. TOH w/1 1/4 workstring. Pull free point & cut off 4 1/2 csg @ 1035. Work pipe would not pull free, cut off @ 830'. Pmp 50 sxs from 830-680'. Pmp 30 sxs from 475-375'. Pmp 10 sxs from 40-0', pull 20 jts 4 1/2 csg. Cut off & cap 8 5/8 csg 3' below ground level.
(If additional description is necessary, use BACK of this form.) KCC witnessed. Restore location.

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Technical Assistant (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

(Address) Beverly J. Williams, Tech. Asst.
P.O. Box 351, Liberal, KS 67905

SUBSCRIBED AND SWORN TO before me this 27th day of April, 19 93

Cheryl Steers
Notary Public

My Commission Expires:

CHERYL STEERS
My Appt. Expires 10-1-93