

15-129-10414-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME INTERSTATE UNIT*

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER 39

1980 Ft. from S Section Line

4620 Ft. from E Section Line

SEC. 20 TWP. 34SRGE. 43 (W)

COUNTY Morton

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Date Well Completed 1/14/56

Character of Well Input

Plugging Commenced 9/25/87

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Completed 9/26/87

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City

Is ACO-1 filed? NA If not, is well log attached? Driller's Log Attached

Producing Formation Morrow Depth to Top 4184 Bottom 4212 T.D. 4260

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Morrow	Oil	0	1140	8-5/8	1140	-0-
		0	4259	5-1/2	4259	1135

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Spotted 2 sxs of hulls mixed w/gel followed by 50 sxs common cmt from 4223-3780. Load hole w/lease wtr. Shot off csg @ 1135, spotted 70 sxs cmt 1135-900, spot 35 sxs cmt 600-500, push wooden wiper plug to 40. Pump 10 sxs cmt 40-3, cut off csg and cap well. 9 ppg mud was spotted between each plug.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901


STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Production Manager (Employee of Operator) or ~~KXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

*Formerly J.M. Huber Corporation
Interstate Block "A" No. 11
(Address) P. O. Box 351, Liberal, Kansas 67901

SUBSCRIBED AND SWORN TO before me this 9th day of November, 1987



Beverly J. Williams
Notary Public
STATE CORPORATION COMMISSION

NOV 12 1987 Form CP-4
Revised 07-86

CONSERVATION DIVISION
Wichita, Kansas

Well Log

Huber #11 Interstate Well

Location: Sec. 20-34-43, Morton County, Kansas

Operator: J. M. Huber Corporation

Contractor: Holm Drilling Company

Commenced: 11-20-55

Spud: 11-22-55

Rotary Work Completed: 12-5-55

Rotary Depth: 4260'

Casing Record: 13 3/8" set at 75' Ground Level
 8 5/8" set at 1134'
 5 1/2" set at 4259'

<u>Formation</u>	<u>Depth</u>
Sand, Shale and Shells	275'
Shale and Shells	640'
Gyp	675'
Shale and Shells	740'
Gyp	775'
Shale and Shells	940'
Shale and Anhydrite	1140'
Shale and Shells	1200'
Anhydrites	1220'
Shale and Shells	2355'
Lime and Shale	2417'
Lime	2535'
Lime and Shale	2840'
Lime and Sand	2865'
Lime and Shale	2970'
Lime	3130'
Lime and Shale	3819'
Lime	3975'
Lime and Chirt	4070'
Lime	4140'
Shale	4150'
Shale and Sand	4190'
Sand	4210'
Sand and Lime	4260' T. D.

Certified Copy of Well Log
 HOLM DRILLING COMPANY

RECEIVED
 STATE CORPORATION COMMISSION

By

[Handwritten Signature]

SEP 24 1987

STATE CORPORATION COMMISSION