

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

15-129-10409-0000

API NUMBER 11-12-55 drill date

LEASE NAME Interstate Unit

WELL NUMBER 40

1980 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 20 TWP. 34S RGE. 43 XX or (W)

COUNTY Morton

Date Well Completed 12-7-55

Plugging Commenced 7-11-92

Plugging Completed 7-15-92

TYPE OR PRINT

NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67905-0351

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

The plugging proposal was approved on 7-10-92 (date)

by Glenn Barlow (KCC District Agent's Name).

Is ACO-1 filed? Yes If not, is well log attached? -

Producing Formation Morrow Depth to Top 4162 Bottom 4181 T.D.

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8 5/8	1016	0
				5 1/2	4222	1225'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. Pull 200' tbg. Circ hole w/mud. Pmp 1 sk hulls & 20 sxs cmt 4162-4062. TOH w/2 3/8 tbg. Pmp 50 sxs cmt @ 1050-950, 40 sxs cmt @ 650-550, 10 sxs cmt @ 40-3'. Cut off 8 5/8 csg 3' below ground level & cap well. Recovered 1225' 5 1/2 csg. Restore location. KCC witnessed.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargent's Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901

NAME OF PARTY RESPONSIBLE FOR PLUGGING FEES: Anadarko Petroleum Corporation

STATE OF Kansas COUNTY OF Seward, ss.

Beverly J. Williams, Engineering Technician (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and received herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Beverly J. Williams

(Address) P.O. Box 351, Liberal, KS 67905-0351

AUG 11 1992

SUBSCRIBED AND SWORN TO before me this 4th day of August, 19 92
CONSERVATION DIVISION
WICHITA, KS

Cheryl Steers
Notary Public

My Commission Expires:

