

15-129-10408-0000

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER NA

LEASE NAME INTERSTATE UNIT*

WELL NUMBER 34

3300 Ft. from S Section Line

3300 Ft. from E Section Line

SEC. 20 TWP. 34S RGE. 43 (X) or (W)

COUNTY Morton

Date Well Completed 11/11/55

Plugging Commenced 9/25/87

Plugging Completed 9/29/87

LEASE OPERATOR Anadarko Petroleum Corporation

ADDRESS P. O. Box 351, Liberal, Kansas 67901

PHONE#(316) 624-6253 OPERATORS LICENSE NO. 4549

Character of Well Oil

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC District Office prior to plugging this well? yes

Which KCC Office did you notify? Dodge City

Is ACO-1 filed? NA If not, is well log attached? Driller's Log Attached

Producing Formation Morrow Depth to Top 4172 Bottom 4198 T.D. 4552

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
<u>Morrow</u>	<u>Oil</u>	<u>0</u>	<u>1193</u>	<u>8-5/8</u>	<u>1193</u>	<u>-0-</u>
		<u>0</u>	<u>4300</u>	<u>5-1/2</u>	<u>4300</u>	<u>1200</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set. CIBP set @ 4060. Spotted 25 sxs common cmt 4060-3770 on top of CIBP. Loaded hole w/lease water. Shot off csg @ 1200, spotted 70 sxs cmt 1200-1050, spotted 25 sxs cmt 650-550, push wooden wiper plug to 40, pmp 10 sxs cmt 40-3, cut off csg and cap well. 9 ppg mud spotted between each plug.

(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sargents Casing Pulling Service License No. 6547

Address 620 S. Lincoln, Liberal, Kansas 67901


STATE OF KANSAS COUNTY OF SEWARD, ss.

M. L. Pease, Division Production Manager (Employee of Operator) or ~~XXXXXXXXXX~~ of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) M. L. Pease

*Formerly J.M. Huber Corporation
Interstate Block "A" No.5 (Address) P. O. Box 351, Liberal, Kansas 67901

SUBSCRIBED AND SWORN TO before me this 11th day of November, 19 87



Beverly J. Williams
Notary Public
STATE CORPORATION COMMISSION

Form CP-4
revised 07-86
NOV 12 1987
11-12-87
CONSERVATION DIVISION
Wichita, Kansas

