


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to
Conservation Division
State Corporation Comm.
245 North Water
Wichita, KS 67202



Locate well correctly on above
Section Plot

Morton County, Sec. 20 Twp. 34 Rge. 43 E/W
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines

App. C NE SE S W SE

Lease Owner Anadarko Production Company

Lease Name Interstate Unit Well No. #1 SWDW

Office Address Box 351, Liberal, Kansas 67901

Character of Well (Completed as Oil, Gas or Dry Hole)

SWDW

Date Well completed 10-14 1959

Application for plugging filed 7-13 1978

Application for plugging approved 7-17 1978

Plugging commenced 8-23 1978

Plugging completed 8-23 1978

Reason for abandonment of well or producing formation

Not taking enough water.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Clarence Thomas

Producing formation Glorietta Sand Depth to top 827 Bottom 935 Total Depth of Well 968.5

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	90	None
				4-1/2"	966	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Spotted 75 sacks Common 202' to 0'.

RECEIVED
STATE CORPORATION COMMISSION
DEC - 9 1978

CONSERVATION DIVISION
Wichita, Kansas
12-8-78

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dowell

STATE OF KANSAS COUNTY OF SEWARD, ss.
Paul Campbell (employee of owner) or (owner or operator)
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

Paul Campbell, Div. Prod. Mgr. (Signature)

Box 351, Liberal, Kansas 67901

(Address)

SUBSCRIBED AND SWORN TO before me this 7th day of December, 1978



BEVERLY J. WILLIAMS
Seward County, Kansas
My Appt. Exp. 11/21/82

My commission expires

November 21, 1982

Beverly J. Williams
Notary Public.

DRILLER LOG

OPERATOR: J. M. Huber Corp.
 Block A Lease
 Salt Water Disposal Well
 LOCATION: Sec. 20-34S-43W
 1466' from E line & 504'
 from S line of sec. 20
 Morton County, Kansas

CONTRACTOR: Carlile Water Well
 Service
 CONN: 10-10-59
 COMP: 10-14-59
 Remarks: Set 90' 8 5/8" Spiral
 Weld Csg. cemented w/
 75 sx. pozmix w/4 sx.
 HA-5 blended 3%.
 Set 966' 4 1/2" 10 thd.
 9.5# Csg. w/260 sx.
 Pozmix.

FORMATION:

Sand	0-21'
Clay	21-40'
Sand	40-46'
Clay	46-60'
Sand & Clay Streak	60-74'
Red Clay	74-93'
Red Bed	93-148'
Sandy Red Bed	148-174'
Red Bed Shaly	174-281'
Red Bed (Soft)	281-370'
Red Bed Streak of White Rock	370-482'
Red Bed	482-615'
Red Bed Streak of Rock	615-637'
White Rock & Chalk (Hard)	637-704'
Red Bed Streak of Rock	704-726'
White Rock & Chalk (Hard)	726-802'
Red Bed	802-827'
Glorieta Sand	827-935'
Red Bed	935-968.50'
Total Depth	968.50'

We certify the above log is true
 and correct to the best of our
 knowledge and belief.

CARLILE WATER WELL SERVICE

Bernard E. Carlile

Bernard E. Carlile

Subscribed and sworn before me this 8 day of January 1960

[Signature]
 Notary Public

My Commission expires February 9, 1963