

2040092

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-191-21679-0000

TECHNICIAN'S PLUGGING REPORT

660/1980 feet from (N/S) section line

330 feet from W(E) section line

Operator License # 9584

Lease Name Unruh Well # 1

Operator: Mackellar Inc

County Sumner

Name & Address 2601 NW Expressway Svt 203 E

Well Total Depth 5940 193.05 feet

Oklahoma City Oklahoma

Conductor Pipe: Size _____ feet

7312

Surface Casing: Size 8 5/8 feet 25I

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A

Other well as hereinafter indicated _____

Plugging Contractor Hughes Drilling Co. License Number _____

Address PO Box 6001 Enid Oklahoma

Company to plug at: Hour: 1200 Day: 6 Month: 8 Year: 19 84

Plugging proposal received from Curly Foster

(company name) Mackellar Inc (phone) _____

were: 35 SX 5940

SX 1250

35 SX 300

20 SX 40' on Solid Bridge

10 SX RH

Plugging Proposal Received by Stan De Susi
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part None _____

Operations Completed: Hour: 0530 Day: 8 Month: 6 Year: 19 84

ACTUAL PLUGGING REPORT Filled hole with mud. Ran Drill pipe to 5940' and spotted 35 sacks of cement, displaced with mud. Pipe was pulled to 1250' and the pits were emptied down the hole. It is unknown if the bottom is still in the hole. The next plug was spotted at 1250' with 35 sacks of cement. The pipe was pulled to 300' and 35 sacks

Remarks: _____ HowCO778479

(If additional description is necessary, use BACK of this form.)

I (did / did not) observe this plugging.

STATE CORPORATION COMMISSION

6-27-84

JUN 20 1984

Signed S.V.

2148

CONSERVATION DIVISION
Wichita, Kansas

WL

(TECHNICIAN)

RO

was spotted there. Pipe was pulled from hole and a
solid bridge was set at 40' and 20 sack of cement was
spotted on bridge. 10 sack was circulated thru Drill pipe
in the Rat hole. Job by HOWCO # 778479
6-8-84 0530.