

15-191-21501-0000 *R*

2 070300

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- old well
SESESW, SEC. 4, 7 35 S, R 1 W/EX
_____ feet from N/S section line
_____ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5360

Lease Name Cottel Well # 1-A

Operator: Brandt Production Co., Inc.
Name & Address 105 S. Broadway St. 920
Wichita, KS 67202

County Sumner 148.69

Well Total Depth 4575 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 395

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor B & S Well Service License Number 6013

Address Winfield, KS

Company to plug at: Hour: _____ Day: 24 Month: 9 Year: 19 85

Plugging proposal received from _____

(company name) _____ (phone) _____

were: 5 1/2" set at 4132 feet, plug back to 4060 and perf at 4008-18 - plug back to 3700 feet - perf at 3456 to 69 - push plug to 3500 feet - fill with rock to 3400 feet and dump 6 sack of cement - shoot and pull pipe

Plugging Proposal Received by Glenn Ward
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 3:00p.m. Day: 24 Month: 9 Year: 19 85

ACTUAL PLUGGING REPORT Pushed plug to 3500 feet and filled with rock to 3400 feet. Dumped 6 sacks of cement. Shot and pulled 2478 feet of 5 1/2" casing. Ran 2" tubing to 448 feet and circulated hole full of cement to surface with 150 sacks of Class "A" cement.

Remarks: United #0106
(if additional description is necessary, use BACK of this form.)

RECEIVED
OCT 10 1985
10-10-85
10423

WK

STATE CORPORATION COMMISSION
CONSERVATION DIVISION
Wichita, Kansas

Signed Glenn Ward
(TECHNICIAN)

RD