

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-025-20,396-0000 57
100' S of
C SW NW, SEC. 7, T. 35, R. 21 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5654

3200 feet from S section line

4620 feet from E section line

Operator: Rine Drilling Company

Lease Name Tuttle Well # 1-7

Name & Address 300 W. Douglas, Suite 600

County Clark 185.05

Wichita, KS 67202

Well Total Depth 5694 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 860

Abandoned Oil Well _____ Gas Well Input Well _____ SHD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Kelso Casing Pulling, Inc. License Number 6050

Address P.O. Box 347, Chase, KS 67524

Company to plug at: Hour: 12 p.m. Day: 13 Month: 5 Year: 19 91

Plugging proposal received from Bill Fulls

(company name) Kelso Casing Pulling, Inc. (phone) 316-938-2943

were: 4 1/2" at 5694', PBTD 5693', Perfs at 5554'

1st plug sand back to 5500' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls,

release 8 5/8" wiper plug and pump 100 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 1:15 p.m. Day: 13 Month: 5 Year: 19 91

ACTUAL PLUGGING REPORT 1st plug sanded back to 5800' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped 300 lbs. hulls, 15 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 100 sx cement.

Maximum pressure 900 psi and shut in 600 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 3400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

RECEIVED

I (did / did not) observe this plugging operation
STATE CORPORATION COMMISSION

5-24-91
31901

Signed Richard M. Lacey
(TECHNICIAN)

MAY 15 1991

CONSERVATION DIVISION
Wichita, Kansas

FORM CP-2/3
Rev. 01-84